

All materials required for the work shall be supplied by the contractor as per standard specifications appended with due approval by the Engineer in charge of G.P.H. Wing. In case the materials as per make specified are not available, the materials of equivalent make and as per I.S. Specifications or of best quality when not covered by I.S. Specifications can be utilized on prior approval of concerned S.E./ E.E., GPHD (R&B) Circle/Division or the officers duly authorized. It is binding on the part of the contractor to use such items of materials which are available in the Departmental store and in such case the deduction from the bills will be made at stock issue rates.

TECHNICAL SPECIFICATION OF INTERNAL ELECTRIFICATION WORKS

The details of internal wiring, the position of fittings, fans, switches and plug sockets etc. are indicated in the layout drawings. The position of light fittings, fans, switchboards etc. indicated in these drawings are only for the guidance of the supplier and the actual position of these shall be mutually decided between the supplier and the purchaser. The supplier shall submit the purchaser of his consideration and approval all runs of wiring and the exact position of all the points and the switch boxes first marked on the points buildings.

All internal wiring shall be done in conformity to the latest Indian standard specification/Rules, code of practice adopted by CPWD and other standard practices prevalent in the part of the country. For the purpose of the specification the terminology used shall be as defined in IS:732 and IS:1356 of the definition of points wiring. The installation shall be carried out in conformity to all requirements of IE Act, 1910 and IE Rules 1956.

- a) Ceiling rose in (in case of ceiling and exhaust fan).
 - b) Ceiling rose or connector (in case of pendants except stiff pendant points)
 - c) Bank plate (in case of stiff pendant).
 - d) Socket outlet (in case of socket outlet points)
 - e) Lamps holder (in case of wall Bracket, batten holder bulk head fitting and similar other fittings)
 - f) Call bell / buzzer (in case words 'via' the switch shall be read 'via' the ceiling rose / socket outlet for bell push, where no ceiling rose / socket outlet its provided.
- The following shall be deemed to be included in the point wiring
- a) Switch and ceiling rose are required
 - b) In case of wall brackets, bulk head fittings, cables as required up to the lamp holders]
 - c) Bushed conduit for porcelain tubing where cables pass through walls.
 - d) All wood or metal blocks, boards and boxes, R.J. Boxes sunks or surface type including those required for fan regulator but excluding those under the distribution board and main control switch.
 - e) Earth wire from 3 pin socket point to the common earth including connection to the earth dolley.
 - f) Earth wire of 16SWG/14 SWG/I.G. wire for loop earthing of the fixture
 - g) All fixing accessories such as clips, nails, screw, plug, rawl plug, wooden plug, round blocks etc. as required
 - h) Joint for junction boxes and connecting the same as required
 - i) Connections to ceiling rose or connection socket outlet, lamp holders, switch, fan regulators etc

The point wiring in case of fan and light points shall mean the distance between the control switch and ceiling rose, connect or back plate, socket outlet or lamp holder depending upon the fittings measured along the runs of wiring irrespective of the number of wires in run. In the case of socket outlet points, the length shall mean the distance between the socke

In the case of exclusive socket outlet circuits wired on 'Joint Box' system of wiring, any junction provided for extending the wiring beyond the point referred to, shall be treated as the nearest tapping point. In case of call bell / buzzer points the length shall mean the distance between the call bell and the ceiling rose / socket outlet or the bell push (when the ceiling rose / socket outlet is not used).

Sub main shall include the earth wire of adequate size main distribution Board up to sub distribution board B.B. such wiring has been classified on the basis of length. For the internal lighting, either surface conduct wiring system or recessed conduit or batten wiring system shall be provided as specific in the bill of quantities and working drawings.

LED LIGHTS

- 1 LED light distribution pattern, illuminance, Luminous flux, chromaticity, color temperature, color rendering Index to applicable standard Lm79 & Lm80.
- 2 LED lights should be as per standards IEC EN 60598 and IEC61547.
- 3 LED luminaires should function in a temperature range -30°C + 60°C under 95% relative humidity condition to simulate adverse operating environment.
- 4 The LED produces should meet safety standards as per EN60598, EMCIEMI standard as per EN611547/EN 55015 and EN61000-3-2 and 61000-3-3 for Harmonics.
- 5 The electronic driver should work in the short circuit and open circuit conditions and should work in the voltage range 90V to 3000 volts.
- 6 LED lighting fixtures should be manufactures with LEDs of on only reputed makes such as Cree, Samsung, Lumiled osram and other equivalent.
- 7 The officer-in-charge has reserve the right to inspect and tested the quality in Govt. laboratory to ensure technical qualifications to meet the requirements.
- 8 LED lights no toxic materials U V and IR spectrum protects insect life.
- 9 It should be manufacture with dia-cast aluminium with required colour as per manufacture for released months.
- 10 The LED lights Should function 90 to 380V, 50/60 Hz, PF-0.9 (230V AC), Copper temp-3000K/4000K/ 6000K/ operation temperature - 20°C + 50°C in-gross protection-IP 20, lifespan 30000hrs.

Firefighting

- 1 No advance payment will be made by the Department. However Part / full Payment shall be made by the Executive Engineer, General Electrical Division No.II, Cuttack after completion of supply, erection testing and commissioning, inspection and satisfactory operation.
- 2 In the event of failure or refused to execute the order the ISD will be forfeited and the order will be cancelled after the completion time period from the date of issue of the order. In the event of delay in supply erection, testing and commissioning of the materials with work pertaining to order, penalty @ 0.5% of the order value per month delay will be imposed subject to a maximum of 5% (Five percent) along with the EMD.
- 3 All the materials should be ISI marked and duly approved by the fire Deptt. Govt. of Odisha.
- 4 3rd Party Audit should be done by registred agency of Fire Deptt. Govt. of Odisha by the firm
- 5 Drawing and designed duly approved by the Fire Deptt. Govt. of Odisha should be submitted before execution of work.
- 6 If addition alternation required as per guide line of Fire Deptt., the fire will execute the same with due approval of the authority.
- 7 After completion of the work the firm should made a mock fire drill demonstration in presence of Engineer-in-Charge, authorised officer of the Fire Deptt. and building authority.

A.C. Machine

- 1 The tenders should furnish following documents in cover-1.
- 2 Detail drawing and design.
- 3 Technical specification as per manufactures norms supp.
- 4 Detail of equipments and material supplied.
- 5 Make, model with individual price may be furnished.
- 6 All the materials and equipments must be confirming to ISI.

Lighting arrester



Supply, Installation, Testing and Commissioning of Copper Plate Earthing (600x600x3mm) with running Copper Flat 25x5mm from copper plate to funnel of 40mm dia GI PIPE heavy duty with including all accessories, excavation of earth and providing masonry work with cover plate having locking arrangement and and , charcoal, salt , funnel , tinned brass bolt, check nut and washer complete in all respect as per Direction of Engineering -in-Charge.

D.G. Set

DG set should be capable of running continuously for unlimited hours in a year, stopping required only for service duration

Diesel Engine

Duty : Continuous running

Type: 4Stroke, Turbo Charged, aftercooled

Capacity: 32 Liter.

Cooling: Radiator

Governing: Full electronic

Fuel injection: Electronic Unit injectors

Alternator :

Rating: 1010 KVA/808 KW at 415 volt, 0.8pf, 50Hz, 3phase, 4wire@1500rpm.

Duty: Continuous running

Type: Self excited, self regulated, single bearing, IP-23

Efficiency:92%

- Above engine alternator should be assembled on a steel fabricated common base frame.
- Five sided Acoustic enclosure would be required to reduce noise.
- 990 L fuel tank would be placed outside acoustic enclosure.
- 2Nos. 12Volt, 180AH reputed make batteries.
- Set of Antivibration mountings.
- First fill of engine oil.
- Heavy duty silencer.

Design Criteria

The generator asset meets transient response and block loading steps as per ISO 8528-5

Single-Source Supplier

Fully prototype testes with torsional analysis.

| ACCEPABLE MAKES FOR FIRE FIGHTIG | | |
|----------------------------------|---|--|
| Sl. No. | ITEM | ACCEPTABLE MAKE |
| 1 | PUMP | Kirloskar/Crompton/ABB/Siemens |
| 2 | Motor | Kirloskar/Crompton/ABB/Siemens |
| 3 | Diesel Engine | Kirloskar/Cmmms |
| 4 | M.S.Pipe | TATA/Jindal/Sail/Nzon/(ISI Marked) |
| 5 | G.I.Pie | TATA/Jindal/Sail/Nzon/(ISI Marked) |
| 6 | C.I.Pipe | IS : 1537 |
| 7 | C.I.Pipe Fitting | IS : 1538 |
| 8 | Sluice Valve | Kirloskar/Leader/Sant/Zolta/(ISI Marked) |
| 9 | Gun Metal Valve | -do- |
| 10 | Butterfly Valve | -do- |
| 11 | Water Solenoid Valve | -do- |
| 12 | Cushy Foot Mountins | ISI Marked |
| 13 | Pressure Switch | ISI Marked |
| 14 | Pressure Gauge | ISI Marked |
| 15 | Water Level Controller | ISI Marked |
| 16 | Batteries | OEM/OEA |
| 17 | Flow Switch | |
| 18 | Internal/External Hydrant (Landing Valve) | Cosmos/Newage/Jayshree/GETECH |
| 19 | Hose Reel 20mm Dia. | -do- |
| 20 | Installation Control Valve | -do- |

| | | |
|--------------------------------------|---|--------------------------------------|
| 21 | Fire Bridge Intel/Connection | -do- |
| 22 | Sprinkler Head | -do- |
| 23 | RRL Hose Pipe 63mm Dia. | -do- |
| 24 | GM Branch Pipe 63mm x 20mm Dia. | -do- |
| 25 | First Aid Hose Reel Drum | -do- |
| 26 | Power Cables | Havell's/Finolex/Mescab/Polycab |
| 27 | Control Cables | -do- |
| 28 | Single Phase Preventor | L&T/GE/Siemens |
| 29 | SDFU/SFU with HRC Fuses | -do- |
| 30 | Starters/Control | -do- |
| 31 | Electrical Panel/System Controller & Control Console | From CPRI approved panel manufacture |
| ADDRESSABLE FIRE ALARM SYSTEM | | |
| 1 | Microprocessor based Photo electric smoke/Heat Detector | Appolo/Cooper/Honeywell/Edward/L&T |
| 2 | Microprocessor based Manual call Box | -do- |
| 3 | Microprocessor based Control Module | -do- |
| 4 | Fire Alarm Control Panel | -do- |
| 5 | Steel conduit | AKG/BEC/RMCON |
| 6 | FRLS and Twisted Cables | Finolex/Havell's/RR Kable |

Conduit wiring

For recessed conduit wiring system the conduit shall be placed in the ceiling / columns etc. before the casting of the slab or column. The conduit pipes shall be properly positioned and fixed so that it will not be displaced at the time of concreting. The junction boxes provided shall be so arranged that its cover will be flushed with the finished surface of the ceiling or column.

For placing the conduits in the walls, chases of ample dimension shall be made neatly to fix the conduit in a desired manner. The conduit pipe shall be fixed by means of staple or saddles not more than 600mm apart. Fixing of standard bends or elbows shall be avoided and all curves maintained by bending the conduit itself with a long radius will permit easy drawing of the conductors. Suitable inspection boxes shall be provided to permit periodical inspection and removal or replacement of wires if necessary. There shall be mounted flush with the wall with holes in the cover of the box.

The switch or regulator box shall be made of metal on all sides except on the front where backlight sheet or Perspex cover painted to match the colours of the wall shall be used in case of surface wiring system. For recessed wiring system, these boxes shall be made flush with the conduit of each conduit or section shall be completed before conductors are drawn in. The entire system of conduit after installation shall be tested for mechanical strength and electrical continuity throughout the earthing of the entire installation shall be carried out in accordance with I.E. Rules and standards. The number of wires drawn in the conduits shall not exceed the numbers those specified in Indian standard specification No.732.

Main and Sub distribution Boards:

The position of main boards for lighting and sub distribution board for different buildings are approximate and the exact location shall be given to the successful tenderer at the time of installation. The scope of this specification includes installation of the panel boards and distribution boards and making necessary connections. The installation of the boards shall be done strictly in accordance with the details supplied with the specifications; the instructions supplied by the switchgear manufacturer, Indian standard specifications and H.E. rules. The supplier shall submit the details of installations to the purchaser for his consideration and approval, prior to installation.

When the switchboards are wall / column mounted top, they shall, be mounted on a suitable angle iron framework. All the metal supports etc. shall be protected against corrosion. The mounting height for such switchboards shall be such that it can be conveniently operated.

Earthing

Earthing shall generally be carried out in accordance with the requirements of Indian Electricity Rules and the relevant rules and regulations of electrical supply authorities. The complete earthing work for the installation covered by this specifications shall also be provided taking into account Indian Standard Specification No.IS:732 and IS:3043. The earthing system adopted shall also have adequate mechanical strength.

The work shall include earthing of non-current carrying metallic parts of all the equipment, light fittings, conduit pipes, cable and cable supports and earth strips (the design to be approved by the purchaser) and all the inter connection between the earthing system to a value mutually agreed upon\ between the purchasers and the supplier.

Installation, testing and Commissioning:

The supplier shall be responsible for the installation testing the commissioning of all the equipment and materials supplied by him against this specification. This shall also include the provision of miscellaneous wiring and supports and earthing in compliance with Indian Electricity rules and to the full satisfaction of the Government Electrical Inspector. All small items such as clamps, bolts, nuts, racks, supports, miscellaneous wiring etc. required to make the installation complete, shall constitute the part of major items specified in the bill of quantities and the tenderer should quote for each item taking these into consideration.

The responsibility of the supplier shall include receiving all the equipment and materials at site, storage for required period, handling the same at the site of erection, final execution , erections, revisions of equipment, if any, testing and commissioning and handing over the installation complete in all respect to the entire satisfaction of the purchaser's authorized representative. The supplier shall make good of all the damaged equipment and materials during this period at his own expense. The supplier shall submit sample 79 of each and every equipment and materials for the final approval of the purchaser's representatives immediately after the acceptance of offer. All the equipments and materials shall be supplied exactly as per to the approved samples. If at any stage the purchaser brings to the notice of the supplier any discrepancy or defect the supplier shall replace the same at his own expense.

The supplier shall render all reasonable assistance to the purchaser in getting the installation approved by the Government Electrical Inspector prior to the energisation and supply necessary drawings, test certificates and both for tests carried out at the factory and site as well as the tests which the inspector may demand. In case any addition of alternations are required, to be made in the installation or in the equipment as per the directive of the Government Electrical Inspector / Local Authorities, the same will have to be carried out by the supplier , at his own expense.

The position of light fittings, main board, switches, sockets and routes of pipes and cables shown in the drawings are only indicative. The actual position of these shall be decided at site at the time of execution joints by the supplier and the purchaser's authorized representative. The position of light fittings, pipes and board if required, to be changed / shifted due to the change in the building design etc by the purchaser's authorized representative, the same shall be carried out at no extra cost.

All the materials supplied to the contractor according to the Contract condition will be subject to inspection and approval of the officer or his representative from time to time. The contractor will provide all facilities of such inspections free of cost. At the time of inspection, the owner of his representative will have full liberty to reject any such materials, which does not conform to the specification / requirement. No claim for any rejected materials will be entertained by the owner. The contractor will remove all rejected materials from site at his own cost. No surplus materials procured by the contractor will be accepted by the owner. The contractor will be responsible to get the Electric installations cleared by the Electrical Inspector of Odisha Government. Only the inspection fee will be reimbursed by Department on production of challan copy.

Installation and Maintenance Tools:

The supplier along with the tender shall furnish a complete list of tools, appliances and accessories required for the installations of switch gear, light fittings, pipes cables and wires.

Drawings:



All drawings, test certificates, instructions manuals etc. shall be in English Language and all dimensions and weights shall be in metric units.

The tenderer shall submit with the tender general arrangement drawings for the installations work, typical methods and cabling and cables supports pipe work and pipe supports, typical methods of earthing and fixing of light fittings earthing etc. as offered by him in the tender.

The contractor shall submit for the purchaser's approval all layout, the general arrangement drawings as well as the typical details of all types of installation work in three sets before commencing the manufacture and the site installations work well in advance so that the site work shall not suffer.

After obtaining approval of the above drawings the contractor shall supply three sets of the following drawings:

- (a) The arrangement and support of conduit pipe
- (b) The position of light fittings, switches / plug socket and switch boards
- (c) Earthing installations
- (d) Layout plan showing the entire cable network

On completion of work, the successful tenderer shall supply one set of tracing in transparent linen and five sets of prints of all drawings incorporating all the changes / modifications affected during the execution of the contract. All wiring diagrams shall indicate clearly, the switch board, the runs of main and sub main wiring and the position of all the points with their controls. All the circuits shall be clearly indicated and numbered in accordance with IS:375. The technical literatures and operating instructions and the maintenance manuals shall also be supplied in triplicate to the purchasers after the completion of the installations work.

Test:

Manufactures standard tests in accordance with Indian Standard and other standards, adopted shall be carried out on all the equipment and accessories covered by this specification so as to ensure efficient and satisfactory performances of all the components and also the equipment as a whole under working conditions at site. The tenderer shall submit a complete list of all such tests. If the purchaser, if so desired for special tests, to be carried out, under certain conditions the same shall be made by the successful tenderer at his own expenses. All equipment shall be tested at site before the commissioning in accordance with the adopted standard and Indian Electricity Rules. Voltage test shall be carried out on each circuit on completion of wiring and cabling.

Technical Data:

The tenderers shall submit with their tender all such technical data, which are required for complete evaluation of the equipment offered. The suppliers shall give complete technical information of the equipment as detailed in Annexure and relevant Indian standards. The tenderer should supply such details of all equipment and materials offered specially with regard to the following.

- a) Fuse switch board and distribution boards
- b) Light fittings
- c) Conduits and the accessories for them
- d) Switches / plug sockets
- e) Cable and wires

The tender shall give along with his tender the following details:

- a) Complete details of earthing electrodes, earthing station and earthing conductors
- b) Details of conduit supports
- c) Details of all the equipment and accessories to be supplied

Exception to Specifications:

The object of this specification is to have all tenderers quote for equivalent materials and workmanship. It is, however, understood the certain manufacturers may not be able to offer as specified in every case, where the tenderer may find it necessary to deviate from the exact letter and not the intent of the specification, he must specifically state what these deviations may be at the time he submits the tender. All deviations must be grouped in one statement. No deviations other than those included in the tender will be permitted.

PVC insulated Cables and Wires:



For 415V Distribution system, cables of voltage grade not less than 1000V shall be used. These cables shall be heavy-duty class, PVC insulated and PVC sheathed with aluminium/ copper conductors. The wires used in the lighting installation shall be PVC insulated and PVC sheathed copper / aluminium wire in case of conduits wiring and of 660V grade. Wires of different colours shall be made use of for quick\ identification of phase wire / neutral wire etc. All cable of wires shall comply with the requirements regarding the manufacture and testing etc as specified in India Standard Specification IS: 1554 and IS:694.

The length of cables indicated in the bill of quantities and drawings are only indicative and the Successful tenderer will be paid for the exact length of cables laid at site. No joint shall be allowed in a run of cables, which can be covered by a possible drum length of cables.

Fuse switch / switch fuse shall be metalclad dust and vermin proof suitable for use under climatic conditions prevailing at site. Switch fuse / fuse switch units shall comply in general to IS:1567/4064 with regard to design and constructional / features.

The 'ON' and 'OFF' position of the switch handles shall be distinctly indicated and interlocks shall be provided to ensure that the switch cover cannot be opened unless the switch is in the 'OFF' position. Means shall, however, be provided for releasing the interlock to permit closing of switch with cover open for testing purposes. Designs with normal conventional position of switch handles, i.e. with switch handle up in the 'ON' position and down in the 'OFF' position shall be preferred. All live parts inside the switch shall be properly surrounded and inter phase barrier shall be provided.

Switch fuse / fuse switch units, distribution boards shall be provided with necessary metal frame work so that they can be mounted on wall / columns structure etc. as desired. The panel boards, shall be wall mounted type or floor mounted type as specified in the bill of quantities or drawings. Necessary supporting metal frame of approved design shall be provided for all panel boards

The arrangements of work boards shall be such that the operational handle of the top mounted switches are within the convenient of operators (about 1.2 M from the finished floor level) and proper space shall be provided for the termination of the cable in the switches provided below the bus-bars.

The bus-bars within the bus-bar chamber shall be liberally spaced for taking the riser connection. The bus bars with aluminium conductors shall be provided and PVC sleeves of different colour shall be mounted on them for easy identification, Clamped joints for taking the riser connections, instead of bolted type shall be preferred.

Two bolted type earthing terminals shall be provided on the switch boards. All individual switches shall be connected with suitable size earth wire to the main earthing terminals of the switchboard. Hanger Board and shock treatment / charts shall be supplied wherever required. At the incoming side of each pen phase, 3-neon type indicating lamps should be provided at the main board.

Switches and Plug Sockets

Switches provided for control of light points shall conform to IS:1087 and shall be rated for 5A/15A 250V

Ceiling Fans and Exhaust Fans:

Ceiling fans shall conform to Indian standard specification IS: 374-1960. The fans shall be supplied with all standard accessories like regulator and capacitors etc.

The performances rating of the propeller fans shall in accordance with stipulations of IS:2312. All fans shall be robust in design and construction and shall be supplied complete with wall brackets / clamps etc.

Fluorescent Fittings:

All fluorescent fittings supplied shall confirm in general to IS:1913 and shall be complete with all standard accessories like choke, starter and capacitor etc. The type of enclosure provided for the fittings shall be of that specified in the bill of quantities and the working drawings. The materials of construction for fittings used for outdoor installations and for use in the work anodes shall be such that they shall withstand the atmospheric condition in that area. Lamp holders used shall be fully shock proof, spring-loaded rotary type to ensure positive lamp locking. It should also be not possible to touch live parts of the lamp holder both after the lamp has been taken out and during the insertion or removal of the lamp. The starters shall be designed to give designed starting characteristics that shall promote full lamp life. Starter shall have high mechanical strength and topic proof construction. It should be incorporated with radio suppression capacitor o adequate rating and\ capacity. Power factor improvement capacitors are provided with hermetically sealed housing to ensure long and trouble free service. Terminal soldering tango shall be provided for easy electrical connections. The capacitors in general shall confirm to IS:1569-1963 and P.F improvement up to 0.95 for twin fluorescent light fittings and 0.9 for single fluorescent light fittings is to be maintained.

The ballast provided in the fluorescent fittings shall generally be in accordance to IS:1534. The ballast should incorporate the following design features.

- i) Low working temperature
- ii) Correct pre heating current for the electrodes
- iii) Proper wave foam
- iv) Small in dimensions
- v) Correct power supply to the lamp
- vi) No hum.
- vii) Easy connection leads.

All the metal construction of the fittings shall be such that they shall:

- 1) Withstand the atmospheric condition prevailing in the area
- 2) Provide maximum mechanical protection to the tubes and fittings accessories. Assists in maximum and uniform light distribution. All fittings shall be provided complete with florescent lamps. All lamps shall confirm to IS:2418.

Incandescent Fittings:

The incandescent fittings shall be supplied strictly as per the details given in the enclosed annexure and bill of quantities, deviation if any regarding design, construction of materials should be specified clearly. All the metal parts used in construction of the fittings shall have no effect due to dust / fumes / gases likely to exist in the atmosphere. All the bolts, clamps, nuts and guard wire etc shall be galvanized. The wall fittings shall be provided with necessary hooks / clamps / supports etc for fixing the light fittings on wall / ceiling etc as detailed in the bill of quantities and the working drawings. Light fittings shall be suitable for connection with 19mm dia. Conduit pipe as required. If fittings are to be connected through PVC cables, glands of adequate size and capacity shall be provided. The lamp holders provided in the fittings shall confirm to IS:1528.

CODES

Codes shall mean the following including the latest ascendants and / or replacement if any.

- a) Indian Boiler Act, 1923 and Rules and Regulations made their under
- b) Indian Electricity Act, 1923 and Rules and Regulations made there under
- c) Indian Factories Act, 1948 and Rules and Regulations made there under
- d) The minimum wages Act
- e) The Women's Compensation Act
- f) The Payment of Wages Act
- g) The Fatal Accident Act
- h) The Industrial Employment Act
- i) The Employment provident Fund Act
- j) Indian Explosive Act 1984 the Rules and Regulations made there under
- k) Indian Petroleum Act 1934, and Rules and Regulations made there under
- l) A.S.M.E. Test Codes
- m) AIRE Test, Codes



- n) American Society of Materials Testing Codes
 - o) Standards of the Indian Standards Institution
 - 1) Low Tension Circuit Breakers : IS 2516-1955 Part I Sec.1
 - 2) Switchgear Bus Bars IS 375-1963
 - 3) HRC fuse links IS 2208-1962
 - 4) Distribution fuse boards IS2675-1966
 - 5) Enclosure for Low Voltage switchgear IS214701962
 - 6) PVC Cables IS1554-1975
 - 7) Tabular fluorescent lamps for Cameral lighting service IS2418-1963
 - 8) Tungsten Filament Lamps for cameral service IS415-1963
 - 9) Ceiling Fans IS274-1966
 - 10) Flood lights IS1947-1961
 - 11) Wall Glass flame-proof electric light fittings IS2206-1962 (Part 1)
 - 12) Water Tight Electric Light Fittings IS3553-1956
 - 13) Steel Boxes for Enclosure of Electrical Accessories IS5133-1969
 - 14) Fittings for Rigid Steel conduit IS2667-1979
 - 15) Rigid steel circuits for electrical wiring IS3837-1966
 - 16) Accessories for Rigid Steel Conduits for Electrical Wiring IS3837-1966
 - 17) Switch Socket Outlets IS3837-1966
 - 18) PVC Wiring IS694-1977
 - 19) Switches for domestic and similar purpose IS3854-1966
 - 20) PVC wiring IS694-1977
 - 21) Call Bell and Buzzers IS2268-1966
 - 22) Straight through joint boxes and leads sleeves or paper insulated cables-EID-0032-1964
 - 23) Earthing IS3043-1966
 - 24) Electrical Wiring installations IS732-1963
 - 25) Switchgear IS3072-1965 (Part I)
 - 26) Lighting protection IS2309 -1969
 - 27) Public Address system IS1882-1962
 - 28) Low Tension switch use units IS4064-1978
 - 29) Code of Practice for Automatic FIRE ALAM system IS2189-1970
 - 30) Specification for Heat Sensitive Fire Detectors IS2175-1977
 - 31) Guide for Safety procedure in Electric work IS5216-1969
 - 32) Rubber Mats for Electric works IS5424-1969
 - p) Other internationally approved standards and / or Rules and Regulations touching the subject matter of the contract
- Tenderer(s) is/are required to submit the information in the following Schedules



SCHEDULE - A

CERTIFICATE OF NO RELATIONSHIP

I/We hereby certify that I/We* am/are* not related(*) to any officer of P.W.D of the rank of Assistant Engineer & above and any officer of the rank of Assistant / Under Secretary and above of the Works Department, Govt. of Odisha I/We* am/are* aware that, if the facts subsequently proved to be false, my/our* contract will be rescinded with forfeiture of E.M.D and security deposit and I/We* shall be liable to make good the loss or damage resulting from such cancellation.

(*) - Strike out which is not applicable

Signature of the Tenderer

Date:- _____



SCHEDULE - B**EXISTING COMMITMENTS AND ON-GOING WORKS :**

| Description n of works | Place & State | Contract No. | Name & Address of Employer | Value of Contract (. In lakh) | Stipulated Period of Completi on | Value of works* remaining to be completed (. In lakh) | Anticipate d date of completi on |
|------------------------------|------------------|-----------------|-------------------------------------|-------------------------------------|---|--|--|
| 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

* The above information is to be certified by the Engineer in Charge / Employer not below the rank of Superintending Engineer / Executive Engineer or equivalent. In case of there is no existing commitment and ongoing works, the bidder shall declare as nil in schedule B.

Signature of the Tenderer

Date:- -----



LIST OF PLANT AND EQUIPMENTS TO BE DEPLOYED ON THE CONTACT WORK
(MINIMUM REQUIREMENT)

| Sl. No. | List of plants and equipments | Requirement | Marks |
|---------|--|-------------|-------|
| 01. | Concrete Mixer (10 marks for each) | 2 Nos. | 20 |
| 02. | Generator (Each having Not less than 33 KVA capacity) | 1 No. | 10 |
| 03. | Needle Vibrator (5 marks for each) | 2 Nos. | 10 |
| 04. | Plate Vibrator (5 marks for each) | 2 Nos. | 10 |
| 05. | Truck/ Tipper (15 marks for each) | 2 Nos. | 30 |
| 06. | Centering & Shuttering Materials | 500 Sqm. | 10 |
| | N.B. | | |
| | Complete staging centering & shuttering arrangement | | |
| | a) For steel centering & shuttering - Should not be older than 5 years from the last date of receipt of tender | | |
| | b) For Wooden / Ply centering & shuttering - Should not be older than 2 years from the last date of receipt of tender | | |
| | c) In case of centering & shuttering materials certificate of the Superintending Engineer / Executive Engineer Or equivalent and higher rank officer of Govt. / Govt. under taking / PSU within 90 days before last date of receipt of tender is allowed | | |
| | (No marks will be awarded if the area of centering & shuttering materials is less than 500 sqm) | | |
| 07. | Water Tanker (Each having 4000 Ltr. Capacity or more) | 1 No. | 10 |
| | | Total = | 100 |

Minimum Pass marks for qualification - 80

NOTE :

1. Capacity of each plant and equipment should be as per specification attached separately.
2. The above equipment should either be owned or availed on long-term lease extended beyond the duration of the work, the authority of which in either case is to be substantiated before award of the work.
3. The equipment mentioned above must be included in Schedule "C" and clearly indicated as "Owned/leased."
4. Apart from the above list, all other machinery/equipments as will be required for satisfactory completion of the work shall have to be deployed by the agency.
5. For deploying additional sophisticated machinery by the agency for completion of the work, no claim shall be entertained.

Signature of the Tenderer

Date:- _____



WORK EXPERIENCE

LIST OF SIMILAR NATURE OF PROJECTS EXECUTED

| Name of Employer | Name of location and name of work | Contract price in Indian Rupees/Agreement no. | Major Items of works | Stipulated date of commencement / completion of the work as per Agreement | Stipulated date of commencement / completion of the work as per Agreement | Value of work actually executed during last 5 financial years | | Reasons for delay in starting/completion, if any |
|------------------|-----------------------------------|---|----------------------|---|---|---|-------|--|
| | | | | | | Financial year | Value | |
| 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |

Note: The above information is to be certified by the Engineer in Charge / Employer not below the rank of Superintending Engineer / Executive Engineer.

Signature of the Tenderer

Date: -----



SCHEDULE - E

INFORMATION REGARDING CURRENT LITIGATION, DEBARRING EXPELLING OF
TENDERED OR ABANDONMENT OF WORK BY THE TENDERER

1. a) Is the tenderer currently involved in any litigation relating to the works. Yes / No

b) If yes: give details:

2. Has the tenderer or any of its constituent partners been debarred/ expelled Yes / No
by any agency in India during the last 5 years

3. a) Has the tenderer or any of its constituent partners failed to perform on Yes / No
any contract work in India during the last 5 years.

b) If yes, give details:

Note:

If any information in this schedule is found to be incorrect or concealed, qualification application will summarily be rejected.

Signature of the Tenderer

Date:- -----



AFFIDAVIT

1. The undersigned do hereby certify that all the statements made in the required attachments are true and correct.
2. The undersigned also hereby certifies that neither my / our firm / company / individuals _____ nor any of its constituent partners have abandoned any road/ bridge/Irrigation /Buildings or other project work in India nor any contract awarded to us for such works have been rescinded during the last five years prior to the date of this bid.
3. The undersigned hereby authorize (s) and request(s) any bank, person, firm or Corporation to furnish pertinent information as deemed necessary and as requested by the Department to verify this statement or regarding my (our) competency and general reputation.
4. The undersigned understands and agrees that further qualifying information may be requested and agree to furnish any such information at the request of the Department.

Signature of the Tenderer

Date:- -----

Title of Officer

Name of Firm

Date:

(Note: The affidavit should be in the above format. Any change in language / structure is not acceptable & liable for rejection)



SCHEDULE - G

**CERTIFICATE OF EMPLOYMENT OF UNEMPLOYED GRADUATE ENGINEER /
DIPLOMA HOLDERS**

(For Super Class / Special Class / 'A' Class Contractors only)

I / We hereby certify that at present, the following Engineering personnel are working with me / in our firm / company and their bio-data are furnished below.

| Sl. No. | Name of Engineering personnel appointed for supervising contractor's work with address | Qualification | Date of Appointment | Monthly emolument | Whether full time engagement and continuous | If they are superannuated / retired / dismissed or removed personnel from state Govt./ Central Govt. / Public Sector Undertaking / private Companies and s or any one ineligible for Government service |
|---------|--|---------------|---------------------|-------------------|---|---|
| 1 | 2 | 3 | 4 | 5 | 6 | 7 |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Signature of the Tenderer

Date:- _____



SAMPLE FORMATS

UNDER TAKING

This is to certify that

1. My firm has neither been associated, directly or indirectly, with the Consultant or with any other entity that has prepared the design, specifications, and other documents for the Project nor has any person associated with been proposed as Project Manager for the Contract.
2. My firm has not engaged any agency and any of its affiliates engaged by the Engineer-in-Charge to provide consulting services for the preparation or supervision of this work.
3. My firm has not engaged any Engineer of gazetted rank employed in Engineering or Administrative duties in an Engineering Department of the Government of Odisha or other gazetted officer retired from Government service during last two years without prior permission of the Government of Odisha in writing on or before submission of this tender. I am aware that my contract is liable to be cancelled if either I or any of my employees is found any time to be such a person who had not obtained the permission of the Government of Odisha as aforesaid.

Signature of the Tenderer

Date:- -----

- Note:
- i. Strike out whichever is not applicable
 - ii. In case any person is under his employment with due permission from Government, the same



RELATIONSHIP DECLARATION

To,

The Chief Administrator, Shree Jagannatha Temple Administrator, Puri.

Subject : CONSTRUCTION OF CELEBRATION MANDAP AT BACKSIDE SHREE PURUSHOTTAMA BHAKTA NIWAS OF SHREE JAGANNATH TEMPLE, PURI.

Reference: Bid Identification No SJTA No. / 2023-24.

Sir,

Pursuant to clause 2 of the ITB, it is to inform that I have relative(s) employed as an Officer in the rank of an Assistant Engineer/Under Secretary under the Works Department. His (Their) details are as follows.

Relationship:

Name :

Designation :

Office :

Address :

Pursuant to clause 2 of the ITB, I am to submit herewith the names of persons who are working under my firm having near relatives to any gazetted officer in the rank of an Assistant Engineer/Under Secretary in the Works Department.

| Sl. No. | Name of the my employee and his designation in the firm | Presently working at | Details of his relatives working in the Department |
|---------|---|----------------------|--|
| | | | Relationship |
| | | | Name: |
| | | | Designation |
| | | | Office |
| | | | Address |
| | | | Relationship |
| | | | Name: |
| | | | Designation |
| | | | Office |
| | | | Address |

I am also duty bound to inform the relationship of any subsequent employment with any gazetted officer in the rank of an Assistant Engineer/Under Secretary in the Works Department. I am aware that any breach of this condition would render my firm liable for penal action for suppression of facts.

Yours Sincerely

Signature of the Tenderer

Date:-

SCHEDULE - I

MEMORANDUM OF UNDERSTANDING

First Party 1 Sri/Smt....., Aged years, S/O-
....., At / P.O. / Dist-..... (hereinafter called the First Part)

AND

Second Party 1 Sri/Smt....., Aged years, S/O-
....., At /
P.O. / Dist-..... (hereinafter called the Second Part) having H.T. / L.T. / M.V. license
registration
No..... valid upto

AND WHEREAS the First Party of 1st part is the managing partner of

AND WHEREAS the First Party willing to appoint the Second Party to execute the E.I.
(including Fire Fighting work) portion for the tender work, "....."

AND WHEREAS the Second Party accepted the offer of First Party.

NOW THIS DEED OF AGREEMENT WITNESSES AS FOLLOWS;


- 1) That, the Second Party shall do all E.I. works, if the tender is awarded to First Party.
- 2) That, the Second Party shall fulfill all the E.I. works as per the tender schedule by instruction of Engineer-in-Charge
- 3) That, the First Party shall receive payment, signing the bill the document for the concerned work
- 4) That, the Second Party shall abide the rules, regulations and specification of E.I. works of above said matter

In witness where of Both the party have signed in presence of
WITNESS

W1 -

W2 -

Total: -70..... pages only APPROVED for70..... pages only

 OSD (Development)
Shree Jagannath Temple, Puri