

Supply, Installation, Testing and Commissioning of Copper Plate Earthing (600x600x3mm) with running Copper Flat 25x5mm from copper plate to funnel of 40mm dia GI PIPE heavy duty with including all accessories, excavation of earth and providing masonry work with cover plate having locking arrangement and and , charcoal, salt , funnel , tinned brass bolt, check nut and washer complete in all respect as per Direction of Engineering -in-Charge.

**D.G. Set**

DG set should be capable of running continuously for unlimited hours in a year, stopping required only for service duration

**Diesel Engine**

Duty : Continuous running

Type: 4Stroke, Turbo Charged, aftercooled

Capacity: 32 Liter.

Cooling: Radiator

Governing: Full electronic

Fuel injection: Electronic Unit injectors

Alternator :

Rating: 1010 KVA/808 KW at 415 volt, 0.8pf, 50Hz, 3phase, 4wire@1500rpm.

Duty: Continuous running

Type: Self excited, self regulated, single bearing, IP-23

Efficiency:92%

- Above engine alternator should be assembled on a steel fabricated common base frame.
- Five sided Acoustic enclosure would be required to reduce noise.
- 990 L fuel tank would be placed outside acoustic enclosure.
- 2Nos. 12Volt, 180AH reputed make batteries.
- Set of Antivibration mountings.
- First fill of engine oil.
- Heavy duty silencer.

**Design Criteria**

The generator asset meets transient response and block loading steps as per ISO 8528-5

Single-Source Supplier

Fully prototype testes with torsional analysis.



Signature of Contractor

Superintending Engineer  
Shree Jagannath Temple

OSD (Development)  
Shree Jagannath Temple



**ACCEPTABLE MAKES FOR FIRE FIGHTING**

S.NO	ITEM	ACCEPTABLE MAKE
1	Pump	Kirloskar / Crompton / ABB / Siemens
2	Motor	Kirloskar / Crompton / ABB / Siemens
3	Diesel Engine	Kirloskar / Cummins
4	M.S. Pipe	Tata / Jindal / Sail/Nizon / (ISI Marked)
5	C.I. Pipe	IS :1537
6	G.I. Pipe	Tata / Jindal / Sail/Nizon / (ISI Marked)
7	C.I. Pipe Fitting	IS :1537
8	Sluice Valve	Kirloskar / Leader / Sant/Zolta / (ISI Marked)
9	Gun Metal Valve	-Do-
10	Butterfly Valve	-Do-
11	Water Solenoid Valve	-Do-
12	Cushy Foot Mountings	ISI Marked
13	Pressure Switch	ISI Marked
14	Pressure Gauge	ISI Marked
15	Water Level Controller	ISI Marked
16	Batteries	OEM/OEA
17	Flow Switch	
18	Internal/External Hydrant (Landing Valve)	Cosmos/ Newage / Jayshree / GETECH
19	Hose Reel 20 mm Dia	-Do-
20	Installation Control Valve	-Do-
21	Fire Bridge Intel / Connection	-Do-
22	Sprinkler Head	-Do-
23	RRL Hose pipe 63 mm Dia	-Do-
24	GM Branch Pipe 63mm x 20mm dia	-Do-
25	First Aid Hose Reel Drum	-Do-
26	Power Cables	Havells / Finolex / Mescom/Polycab
27	Control Cables	-Do-
28	Single Phase Preventor	L&T / GE / Siemens
29	SDFU / SFU with HRC Fuses	-Do-
30	Starters / Control	-Do-
31	Electrical Panel / System Controller & Control Console	From CPRI approved panel manufacture
<b>ADDRESSABLE FIRE ALARM SYSTEM</b>		
01	Microprocessor based Photo electric smoke / Heat Detector	Appolo / Cooper / Honeywell / Edward/L&T
02	Microprocessor based Manual call Box	-Do-
03	Microprocessor based Control Module	-Do-
04	Fire Alarm Control Panel	-Do-
05	Steel Conduit	AKG / BEC/RMCON
06	FRLS and Twisted Cables	Finolex / Havells / RR Kable

**Conduit wiring**

For recessed conduit wiring system the conduit shall be placed in the ceiling / columns etc. before the casting of the slab or column. The conduit pipes shall be properly positioned and fixed so that it will not be displaced at the time of concreting. The junction boxes provided shall be so arranged that its cover will be flushed with the finished surface of the ceiling or column.

For placing the conduits in the walls, chases of ample dimension shall be made neatly to fix the conduit in a desired manner. The conduit pipe shall be fixed by means of staple or saddles not more than 600mm apart. Fixing of standard bends or elbows shall be avoided and all curves maintained by bending the conduit itself with a long radius will permit easy drawing of the conductors. Suitable inspection boxes shall be provided to permit periodical inspection and removal or replacement of wires if necessary. There shall be mounted flush with the wall with holes in the cover of the box.

The switch or regulator box shall be made of metal on all sides except on the front where backlight sheet or Perspex cover painted to match the colours of the wall shall be used in case of surface wiring system. For recessed wiring system, these boxes shall be made flush with the conduit of each conduit or section shall be completed before conductors are drawn in. The entire system of conduit after installation shall be tested for mechanical strength and electrical continuity throughout the earthing of the entire installation shall be carried out in accordance with I.E. Rules and standards. The number of wires drawn in the conduits shall not exceed the numbers those specified in Indian standard specification No.732.

Signature of Contractor

Superintending Engineer  
Shree Jagannath Temple

OSD (Development)  
Shree Jagannath Temple



**Main and Sub distribution Boards:**

The position of main boards for lighting and sub distribution board for different buildings are approximate and the exact location shall be given to the successful tenderer at the time of installation. The scope of this specification includes installation of the panel boards and distribution boards and making necessary connections. The installation of the boards shall be done strictly in accordance with the details supplied with the specifications; the instructions supplied by the switchgear manufacturer, Indian standard specifications and H.E. rules. The supplier shall submit the details of installations to the purchaser for his consideration and approval, prior to installation.

When the switchboards are wall / column mounted top, they shall, be mounted on a suitable angle iron framework. All the metal supports etc. shall be protected against corrosion. The mounting height for such switchboards shall be such that it can be conveniently operated.

**Earthing**

Earthing shall generally be carried out in accordance with the requirements of Indian Electricity Rules and the relevant rules and regulations of electrical supply authorities. The complete earthing work for the installation covered by this specifications shall also be provided taking into account Indian Standard Specification No.IS:732 and IS:3043. The earthing system adopted shall also have adequate mechanical strength.

The work shall include earthing of non-current carrying metallic parts of all the equipment, light fittings, conduit pipes, cable and cable supports and earth strips ( the design to be approved by the purchaser) and all the inter connection between the earthing system to a value mutually agreed upon\ between the purchasers and the supplier.


**Installation, testing and Commissioning:**

The supplier shall be responsible for the installation testing the commissioning of all the equipment and materials supplied by him against this specification. This shall also include the provision of miscellaneous wiring and supports and earthing in compliance with Indian Electricity rules and to the full satisfaction of the Government Electrical Inspector. All small items such as clamps, bolts, nuts, racks, supports, miscellaneous wiring etc. required to make the installation complete, shall constitute the part of major items specified in the bill of quantities and the tenderer should quote for each item taking these into consideration.

The responsibility of the supplier shall include receiving all the equipment and materials at site, storage for required period, handling the same at the site of erection, final execution , erections, revisions of equipment, if any, testing and commissioning and handing over the installation complete in all respect to the entire satisfaction of the purchaser's authorized representative. The supplier shall make good of all the damaged equipment and materials during this period at his own expense. The supplier shall submit sample 79 of each and every equipment and materials for the final approval of the purchaser's representatives immediately after the acceptance of offer. All the equipments and materials shall be supplied exactly as per to the approved samples. If at any stage the purchaser brings to the notice of the supplier any discrepancy or defect the supplier shall replace the same at his own expense.

The supplier shall render all reasonable assistance to the purchaser in getting the installation approved by the Government Electrical Inspector prior to the energisation and supply necessary drawings, test certificates and both for tests carried out at the factory and site as well as the tests which the inspector may demand. In case any addition of alternations are required, to be made in the installation or in the equipment as per the directive of the Government Electrical Inspector / Local Authorities, the same will have to be carried out by the supplier , at his own expense.

Signature of Contractor

  
Superintending Engineer  
Shree Jagannath Temple

OSD (Development)  
Shree Jagannath Temple



The position of light fittings, main board, switches, sockets and routes of pipes and cables shown in the drawings are only indicative. The actual position of these shall be decided at site at the time of execution

joints by the supplier and the purchaser's authorized representative. The position of light fittings, pipes and

board if required, to be changed / shifted due to the change in the building design etc by the purchaser's

authorized representative, the same shall be carried out at no extra cost.

All the materials supplied to the contractor according to the Contract condition will be subject to inspection and approval of the officer or his representative from time to time. The contractor will provide all facilities of such inspections free of cost. At the time of inspection, the owner of his representative will have full liberty to reject any such materials, which does not conform to the specification / requirement. No claim for any rejected materials will be entertained by the owner. The contractor will remove all rejected materials from site at his own cost. No surplus materials procured by the contractor will be accepted by the owner. The contractor will be responsible to get the Electric installations cleared by the Electrical Inspector of Odisha Government. Only the inspection fee will be reimbursed by Department on production of challan copy.

**Installation and Maintenance Tools:**

The supplier along with the tender shall furnish a complete list of tools, appliances and accessories required for the installations of switch grass, light fittings, pipes cables and wires.

**Drawings:**

All drawings, test certificates, instructions manuals etc. shall be in English Language and all dimensions and weights shall be in metric units.

The tenderer shall submit with the tender general arrangement drawings for the installations work, typical methods and cabling and cables supports pipe work and pipe supports, typical methods of earthing and fixing of light fittings earthing etc. as offered by him in the tender.

The contractor shall submit for he purchaser's approval all layout, the general arrangement drawings as well as the typical details of all types of installation work in three sets before commencing the manufacture and the site installations work well in advance so that the site work shall not suffer.


After obtaining approval of the above drawings the contractor shall supply three sets of the following drawings:

- (a) The arrangement and support of conduit pipe
- (b) The position of light fittings, switches / plug socket and switch boards
- (c) Earthing installations
- (d) Layout plan showing the entire cable network

On completion of work, the successful tenderer shall supply one set of tracing in transparent linen and five sets of prints of all drawings incorporating all the changes / modifications affected during the execution of the contract. All wiring diagrams shall indicate clearly, the switch board, the runs of main and sub main wiring and the position of all the points with their controls. All the circuits shall be clearly indicated and numbered in a accordance with IS:375. The technical literatures and operating instructions and the maintenance manuals shall also be supplied in triplicate to the purchasers after the completion of the installations work.

**Test:**

Signature of Contractor

  
Superintending Engineer  
Shree Jagannath Temple

OSD (Development)  
Shree Jagannath Temple



Manufactures standard tests in accordance with Indian Standard and other standards, adopted shall be carried out on all the equipment and accessories covered by this specification so as to ensure efficient and satisfactory performances of all the components and also the equipment as a whole under working conditions at site. The tenderer shall submit a complete list of all such tests. If the purchaser, if so desired for special tests, to be carried out, under certain conditions the same shall be made by the successful tenderer at his own expenses. All equipment shall be tested at site before the commissioning in accordance with the adopted standard and Indian Electricity Rules. Voltage test shall be carried out on each circuit on completion of wiring and cabling.

**Technical Data:**

The tenderers shall submit with their tender all such technical data, which are required for complete evaluation of the equipment offered. The suppliers shall give complete technical information of the equipment as detailed in Annexure and relevant Indian standards. The tenderer should supply such details of all equipment and materials offered specially with regard to the following.

- a) Fuse switch board and distribution boards
- b) Light fittings
- c) Conduits and the accessories for them
- d) Switches / plug sockets
- e) Cable and wires

The tender shall give along with his tender the following details:

- a) Complete details of earthing electrodes, earthing station and earthing conductors
- b) Details of conduit supports
- c) Details of all the equipment and accessories to be supplied

**Exception to Specifications:**

The object of this specification is to have all tenderers quote for equivalent materials and workmanship. It is, however, understood the certain manufacturers may not be able to offer as specified in every case, where the tenderer may find it necessary to deviate from the exact letter and not the intent of the specification, he must specifically state what these deviations may be at the time he submits the tender. All deviations must be grouped in one statement. No deviations other than those includes in the tender will be permitted.

**PVC insulated Cables and Wires:**

For 415V Distribution system, cables of voltage grade not less than 1000V shall be used. These cables shall be heavy-duty class, PVC insulated and PVC sheathed with aluminium/ copper conductors. The wires used in the lighting installation shall be PVC insulated and PVC sheathed copper / aluminium wire in case of conduits wiring and of 660V grade. Wires of different colours shall be made use of for quick\ identification of phase wire / neutral wire etc. All cable of wires shall comply with the requirements regarding the manufacture and testing etc as specified in India Standard Specification IS: 1554 and IS:694.

The length of cables indicated in the bill of quantities and drawings are only indicative and the Successful tenderer will be paid for the exact length of cables laid at site. No joint shall be allowed in a run of cables, which can be covered by a possible drum length of cables.

Fuse switch / switch fuse shall be metalclad dust and vermin proof suitable for use under climatic conditions prevailing at site. Switch fuse / fuse switch units shall comply in general to IS:1567/4064 with regard to design and constructional / features.

The 'ON' and 'OFF' position of the switch handles shall be distinctly indicated and interlocks shall be provided to ensure that the switch cover cannot be opened unless the switch is in the 'OFF' position. Means shall, however, be provided for releasing the interlock to permit closing of switch with cover open for testing purposes. Designs with normal conventional position of switch handles, i.e. with switch handle up in the 'ON' position and down in the 'OFF' position shall be preferred. All live parts inside the switch shall be properly surrounded and inter phase barrier shall be provided.



Superintending Engineer  
Shree Jagannath Temple

Signature of Contractor

OSD (Development)  
Shree Jagannath Temple



Switch fuse / fuse switch units, distribution boards shall be provided with necessary metal frame work so that they can be mounted on wall / columns structure etc. as desired. The panel boards, shall be wall 81 mounted type or floor mounted type as specified in the bill of quantities or drawings. Necessary supporting metal frame of approved design shall be provided for all panel boards

The arrangements of work boards shall be such that the operational handle of the top mounted switches are within the convenient of operators (about 1.2 M from the finished floor level) and proper space shall be provided for the termination of the cable in the switches provided below the bus-bars.

The bus-bars within the bus-bar chamber shall be liberally spaced for taking the riser connection. The bus bars with aluminium conductors shall be provided and PVC sleeves of different colour shall be mounted on them for easy identification, Clamped joints for taking the riser connections, instead of bolted type shall be preferred.

Two bolted type earthing terminals shall be provided on the switch boards. All individual switches shall be connected with suitable size earth wire to the main earthing terminals of the switchboard. Hanger Board and shock treatment / charts shall be supplied wherever required. At the incoming side of each pen phase, 3-neon type indicating lamps should be provided at the main board.

#### Switches and Plug Sockets

Switches provided for control of light points shall conform to IS:1087 and shall be rated for 5A/15A 250V

#### Ceiling Fans and Exhaust Fans:

Ceiling fans shall conform to Indian standard specification IS: 374-1960. The fans shall be supplied with all standard accessories like regulator and capacitors etc.

The performances rating of the propeller fans shall in accordance with stipulations of IS:2312. All fans shall be robust in design and construction and shall be supplied complete with wall brackets / clamps etc.

#### Fluorescent Fittings:

All fluorescent fittings supplied shall confirm in general to IS:1913 and shall be complete with all standard accessories like choke, starter and capacitor etc. The type of enclosure provided for the fittings shall be of that specified in the bill of quantities and the working drawings. The materials of construction for fittings used for outdoor installations and for use in the work anodes shall be such that they shall withstand the atmospheric condition in that area. Lamp holders used shall be fully shock proof, spring-loaded rotary type to ensure positive lamp locking. It should also be not possible to touch live parts of the lamp holder both after the lamp has been taken out and during the insertion or removal of the lamp. The starters shall be designed to give designed starting characteristics that shall promote full lamp life. Starter shall have high mechanical strength and topic proof construction. It should be incorporated with radio suppression capacitor o adequate rating and\ capacity. Power factor improvement capacitors are provided with hermetically sealed housing to ensure long and trouble free service. Terminal soldering tango shall be provided for easy electrical connections. The capacitors in general shall confirm to IS:1569-1963 The ballast provided in the fluorescent fittings shall generally be in accordance to IS:1534. The ballast should incorporate the following design features.

- i) Low working temperature
- ii) Correct pre heating current for the electrodes
- iii) Proper wave foam
- iv) Small in dimensions
- v) Correct power supply to the lamp
- vi) No hum.
- vii) Easy connection leads.

All the metal construction of the fittings shall be such that they shall:

- 1) Withstand the atmospheric condition prevailing in the area
- 2) Provide maximum mechanical protection to the tubes and fittings accessories. Assists in maximum and uniform light distribution. All fittings shall be provided complete with florescent lamps. All lamps shall confirm to IS:2418.

#### Incandescent Fittings:

Signature of Contractor

Superintending Engineer  
Shree Jagannath Temple

OSD (Development)  
Shree Jagannath Temple



The incandescent fittings shall be supplied strictly as per the details given in the enclosed annexure and bill of quantities, deviation if any regarding design, construction of materials should be specified clearly. All the metal parts used in construction of the fittings shall have no effect due to dust / fumes / gases likely to exist in the atmosphere. All the bolts, clamps, nuts and guard wire etc shall be galvanized. The wall fittings shall be provided with necessary hooks / clamps / supports etc for fixing the light fittings on wall / ceiling etc as detailed in the bill of quantities and the working drawings. Light fittings shall be suitable for connection with 19mm dia. Conduit pipe as required. If fittings are to be connected through PVC cables, glands of adequate size and capacity shall be provided. The lamp holders provided in the fittings shall confirm to IS:1528.

### CODES

Codes shall mean the following including the latest ascendants and / or replacement if any.

- a) Indian Boiler Act, 1923 and Rules and Regulations made there under
- b) Indian Electricity Act, 1923 and Rules and Regulations made there under
- c) Indian Factories Act, 1948 and Rules and Regulations made there under
- d) The minimum wages Act
- e) The Women's Compensation Act
- f) The Payment of Wages Act
- g) The Fatal Accident Act
- h) The Industrial Employment Act
- i) The Employment provident Fund Act
- j) Indian Explosive Act 1984 the Rules and Regulations made there under
- k) Indian Petroleum Act 1934, and Rules and Regulations made there under
- l) A.S.M.E. Test Codes
- m) AIRE Test, Codes
- n) American Society of Materials Testing Codes
- o) Standards of the Indian Standards Institution
- 1) Low Tension Circuit Breakers : IS 2516-1955 Part I Sec.1
- 2) Switchgear Bus Bars IS 375-1963
- 3) HRC fuse links IS 2208-1962
- 4) Distribution fuse boards IS2675-1966
- 5) Enclosure for Low Voltage switchgear IS214701962
- 6) PVC Cables IS1554-1975
- 7) Tabular fluorescent lamps for Cameral lighting service IS2418-1963
- 8) Tungsten Filament Lamps for cameral service IS415-1963
- 9) Ceiling Fans IS274-1966
- 10) Flood lights IS1947-1961
- 11) Wall Glass flame-proof electric light fittings IS2206-1962 (Part 1)
- 12) Water Tight Electric Light Fittings IS3553-1956
- 13) Steel Boxes for Enclosure of Electrical Accessories IS5133-1969
- 14) Fittings for Rigid Steel conduit IS2667-1979
- 15) Rigid steel circuits for electrical wiring IS3837-1966
- 16) Accessories for Rigid Steel Conduits for Electrical Wiring IS3837-1966
- 17) Switch Socket Outlets IS3837-1966
- 18) PVC Wiring IS694-1977
- 19) Switches for domestic and similar purpose IS3854-1966
- 20) PVC wiring IS694-1977
- 21) Call Bell and Buzzers IS2268-1966
- 22) Straight through joint boxes and leads sleeves or paper insulated cables-EID-0032-1964
- 23) Earthing IS3043-1966
- 24) Electrical Wiring installations IS732-1963
- 25) Switchgear IS3072-1965 (Part I)
- 26) Lighting protection IS2309 -1969
- 27) Public Address system IS1882-1962

Signature of Contractor

Superintending Engineer  
Shree Jagannath Temple

OSD (Development)  
Shree Jagannath Temple

- 28) Low Tension switch use units IS4064-1978
- 29) Code of Practice for Automatic FIRE ALARM system IS2189-1970
- 30) Specification for Heat Sensitive Fire Detectors IS2175-1977
- 31) Guide for Safety procedure in Electric work IS5216-1969
- 32) Rubber Mats for Electric works IS5424-1969
- p) Other internationally approved standards and / or Rules and Regulations touching the subject matter of the contract

Tenderer(s) is/are required to submit the information in the following Schedules



Signature of Contractor

Superintending Engineer  
Shree Jagannath Temple

OSD (Development)  
Shree Jagannath Temple



**SCHEDULE - A**

**CERTIFICATE OF NO RELATIONSHIP**

I/We hereby certify that I/We\* am/are\* not related(\*) to any officer of P.W.D of the rank of Assistant Engineer & above and any officer of the rank of Assistant / Under Secretary and above of the Works Department, Govt. of Odisha I/We\* am/are\* aware that, if the facts subsequently proved to be false, my/our\* contract will be rescinded with forfeiture of E.M.D and security deposit and I/We\* shall be liable to make good the loss or damage resulting from such cancellation.

(\*) - Strike out which is not applicable

Signature of the Tenderer

Date:- -----



Signature of Contractor

Superintending Engineer  
Shree Jagannath Temple

OSD (Development)  
Shree Jagannath Temple



**SCHEDULE - B****EXISTING COMMITMENTS AND ON-GOING WORKS :**

Description of works	Place & State	Contract No.	Name & Address of Employer	Value of Contract (₹. In lakh)	Stipulated Period of Completion	Value of works* remaining to be completed (₹. In lakh)	Anticipated date of completion
1	2	3	4	5	6	7	8

\* The above information is to be certified by the Engineer in Charge / Employer not below the rank of Superintending Engineer / Executive Engineer or equivalent. In case of there is no existing commitment and ongoing works, the bidder shall declare as nil in schedule B.

Signature of the Tenderer

Date:- \_\_\_\_\_



Superintending Engineer  
Shree Jagannath Temple

Signature of Contractor

OSD (Development)  
Shree Jagannath Temple



**SCHEUDLE -C****LIST OF PLANT AND EQUIPMENTS TO BE DEPLOYED ON THE CONTACT WORK  
(MINIMUM REQUIREMENT)**

Sl. No.	List of plants and equipments	Requirement	Marks
01.	Concrete Mixer (10 marks for each)	2 Nos.	20
02.	Generator (Each having Not less than 33 KVA capacity)	1 No	10
03.	Needle Vibrator (5 marks for each)	2 Nos.	10
04.	Plate Vibrator (5 marks for each)	2 Nos.	10
05.	Truck/ Tipper (15 marks for each)	2 Nos.	30
06.	Centering & Shuttering Materials N.B. Complete staging centering & shuttering arrangement a) For steel centering & shuttering - Should not be older than 5 years from the last date of receipt of tender b) For Wooden / Ply centering & shuttering - Should not be older than 2 years from the last date of receipt of tender c) In case of centering & shuttering materials certificate of the Superintending Engineer / Executive Engineer Or equivalent and higher rank officer of Govt. / Govt. under taking / PSU within 90 days before last date of receipt of tender is allowed. (No marks will be awarded if the area of centering & shuttering materials is less than 500 sqm)	500 sqm.	10
07.	Water Tanker (Each having 4000 Ltr. Capacity or more)	1 No	10
		<b>Total:-</b>	<b>100</b>

Minimum Pass marks for qualification - 80

NOTE :

1. Capacity of each plant and equipment should be as per specification attached separately.
2. The above equipment should either be owned or availed on long-term lease extended beyond the duration of the work, the authority of which in either case is to be substantiated before award of the work.
3. The equipment mentioned above must be included in Schedule "C" and clearly indicated as "Owned/leased."
4. Apart from the above list, all other machinery/equipments as will be required for satisfactory completion of the work shall have to be deployed by the agency.
5. For deploying additional sophisticated machinery by the agency for completion of the work, no claim shall be entertained.

Signature of the Tenderer

Date:- \_\_\_\_\_



Superintending Engineer  
Shree Jagannath Temple

Signature of Contractor

OSD (Development)  
Shree Jagannath Temple



**SCHEDULE - D**

**WORK EXPERIENCE**  
**LIST OF SIMILAR NATURE OF PROJECTS EXECUTED**


Name of Employer	Name of location and name of work	Contract price in Indian Rupees/ Agreement no.	Major Items of works	Stipulated date of commencement / completion of the work as per Agreement	Actual date of completion of the work	Value of work actually executed during last 5 financial years		Reasons for delay in starting/ completion, if any
						Financial year	Value	
1	2	3	4	5	6	7	8	9

Note: The above information is to be certified by the Engineer in Charge / Employer not below the rank of Superintending Engineer / Executive Engineer.

Signature of the Tenderer

Date:- -----

Signature of Contractor

  
 Superintending Engineer  
 Shree Jagannath Temple

OSD (Development)  
 Shree Jagannath Temple



**SCHEDULE - E**

**INFORMATION REGARDING CURRENT LITIGATION, DEBARRING EXPELLING OF TENDERED  
OR ABANDONMENT OF WORK BY THE TENDERER**

1. a) Is the tenderer currently involved in any litigation relating to the works. Yes / No  
b) If yes: give details:
2. Has the tenderer or any of its constituent partners been debarred/ expelled by any agency in India during the last 5 years Yes / No
3. a) Has the tenderer or any of its constituent partners failed to perform on any contract work in India during the last 5 years. Yes / No  
b) If yes, give details:

Note:

If any information in this schedule is found to be incorrect or concealed, qualification application will summarily be rejected.

Signature of the Tenderer

Date:- \_\_\_\_\_



Superintending Engineer  
Shree Jagannath Temple

Signature of Contractor

OSD (Development)  
Shree Jagannath Temple



**SCHEDULE - F****AFFIDAVIT**

1. The undersigned do hereby certify that all the statements made in the required attachments are true and correct.
2. The undersigned also hereby certifies that neither my / our firm / company / individuals \_\_\_\_\_ nor any of its constituent partners have abandoned any road/ bridge/Irrigation /Buildings or other project work in India nor any contract awarded to us for such works have been rescinded during the last five years prior to the date of this bid.
3. The undersigned hereby authorize (s) and request(s) any bank, person, firm or Corporation to furnish pertinent information as deemed necessary and as requested by the Department to verify this statement or regarding my (our) competency and general reputation.
4. The undersigned understands and agrees that further qualifying information may be requested and agree to furnish any such information at the request of the Department.

(Signature of Tenderer)

Title of Officer

Name of Firm

Date:

(Note: The affidavit should be in the above format. Any change in language / structure is not acceptable & liable for rejection)

**SCHEDULE - G****CERTIFICATE OF EMPLOYMENT OF UNEMPLOYED GRADUATE ENGINEER / DIPLOMA HOLDERS**

(For Super Class / Special Class / 'A' Class Contractors only)

I / We hereby certify that at present, the following Engineering personnel are working with me / in our firm / company and their bio-data are furnished below.

Sl. No.	Name of Engineering personnel appointed for supervising contractor's work with address	Qualification	Date of Appointment	Monthly emolument	Whether full time engagement and continuous	If they are superannuated / retired / dismissed or removed personnel from State Govt. / Central Govt. / Public Sector Undertaking / private Companies and is or any one ineligible for Government service
1	2	3	4	5	6	7

Signature of the Tenderer

Date:- \_\_\_\_\_



Superintending Engineer  
Shree Jagannath Temple

Signature of Contractor

OSD (Development)  
Shree Jagannath Temple



**SCHEDULE - H  
SAMPLE FORMATS  
UNDER TAKING**

This is to certify that

1. My firm has neither been associated, directly or indirectly, with the Consultant or with any other entity that has prepared the design, specifications, and other documents for the Project nor has any person associated with been proposed as Project Manager for the Contract.

2. My firm has not engaged any agency and any of its affiliates engaged by the Engineer-in-Charge to provide consulting services for the preparation or supervision of this work.

3. My firm has not engaged any Engineer of gazetted rank employed in Engineering or Administrative duties in an Engineering Department of the Government of Odisha or other gazetted officer retired from Government service during last two years without prior permission of the Government of Odisha in writing on or before submission of this tender. I am aware that my contract is liable to be cancelled if either I or any of my employees is found any time to be such a person who had not obtained the permission of the Government of Odisha as aforesaid.

Signature of the Tenderer

Date:- \_\_\_\_\_

- Note:
- i. Strike out whichever is not applicable
  - ii. In case any person is under his employment with due permission from Government, the same may be cited in a separate letter.



Superintending Engineer  
Shree Jagannath Temple

Signature of Contractor

OSD (Development)  
Shree Jagannath Temple



SCHEDULE - I**RELATIONSHIP DECLARATION**

To,

The Chief Administrator, Shree Jagannatha Temple Administrator, Puri.

Subject: Construction of new Bar Hall with Amenity Center at Sundargarh, Odisha for the year 2023-24.

Reference: Bid Identification No SJTA No. .... / 2023-24.

Sir,

Pursuant to clause 2 of the ITB, it is to inform that I have relative(s) employed as an Officer in the rank of an Assistant Engineer/Under Secretary under the Works Department. His (Their) details are as follows.

Relationship:

Name :

Designation :

Office :

Address :

Pursuant to clause 2 of the ITB, I am to submit herewith the names of persons who are working under my firm having near relatives to any gazetted officer in the rank of an Assistant Engineer/Under Secretary in the Works Department.

Sl No	Name of the my employee and his designation in the firm	Presently working at	Details of his relatives working in the Department
			Relationship Name: Designation Office Address
			Relationship Name: Designation Office Address

I am also duty bound to inform the relationship of any subsequent employment with any gazetted officer in the rank of an Assistant Engineer/Under Secretary in the Works Department. I am aware that any breach of this condition would render my firm liable for penal action for suppression of facts.

Yours Sincerely

Signature of the Tenderer

Date:- .....



Superintending Engineer  
Shree Jagannath Temple

Signature of Contractor

OSD (Development)  
Shree Jagannath Temple



SCHEDULE - I

MEMORANDUM OF UNDERSTANDING

First Party I Sri/Smt....., Aged .... years, S/O-  
....., At / P.O. / Dist..... (hereinafter called the First Part)

AND

Second Party I Sri/Smt....., Aged .... years, S/O-  
....., At /  
P.O. / Dist..... (hereinafter called the Second Part) having H.T. / L.T. / M.V. license  
registration  
No..... valid upto .....

AND WHEREAS the First Party of 1st part is the managing partner of  
.....

AND WHEREAS the First Party willing to appoint the Second Party to execute the  
E.I. (including Fire Fighting work) portion for the tender work, "....."

AND WHEREAS the Second Party accepted the offer of First Party.

**NOW THIS DEED OF AGREEMENT WITNESSES AS FOLLOWS;**


- 1) That, the Second Party shall do all E.I. works, if the tender is awarded to First Party.
- 2) That, the Second Party shall fulfill all the E.I. works as per the tender schedule by instruction of Engineer-in-Charge
- 3) That, the First Party shall receive payment, signing the bill the document for the concerned work
- 4) That, the Second Party shall abide the rules, regulations and specification of E.I. works of above said matter

In witness where of Both the party have signed in presence of  
WITNESS

W1 -

W2 -

Total: - 69 (Sixty Nine) pages only APPROVED for 69 (Sixty Nine) pages only

  
OSD (Development)  
Shree Jagannath Temple, Puri



This agreement made on the ..... Two Thousand between (herein-after referred to as "the hirer" which expression shall unless excluded by or repugnant to the context include his heirs, executors, administrators and assigns) of the one part and the Govt. of Odisha (here in after referred to as the Governor which expression shall unless excluded by or repugnant to the context include his successors in office as assigns) of the other part. Whereas the hirer desirous of hiring the tools and plants of the P.W. Department of the Odisha Govt. and more particularly specified in the schedule here under between here in after referred to as "the tools and plants". And whereas Government has agreed to let in hire the tools and plants to the hirer on the terms and conditions here in after mentioned. Now it is here by and between the parties here to as follows :-

a) In consideration of agreement that hire charges be recovered from their bill for work executed on which this machinery will be used or any other than standing in the names of contractors in the book of the Department or any other Government Department. The Govt. agrees to let the hirer tools and plants for the period to be computed from the date of delivery of the tools and plant to the hirer at the P.W. Department workshop / store at Puri

b) The rate of higher charges will be as mentioned in the schedule attached.

c) The hirer shall not transfer, assign or sublet or in any way part with the tools and plants or any part there-of without the previous written approval of the Engineer-in-charge

d) On the expiry of the period of the hire, the hirer shall return the tools and plants to the Public Works Department. & Workshop / store at Puri in the same good condition in which they were received by him.

e) In the event of the tools and plants not being returned on the expiry of the above-mentioned period, the hirer shall without prejudice and any other liability pay to the Government on account equivalent to the rate of hire specified for the working period and an increase of ten percent.

f) The tools and plants shall be open for inspection at all times to the officers of the Government

g) The hirer shall not operate the tools and plants so hired for more than one shift / two shifts of 8 hours each per day without the prior sanction of the Engineer-in-charge. If the hirer operates the tools and plants beyond the aforesaid limit without the prior sanction of the Assistant Engineer, he shall pay to Government additional hire charges as well as over time charges for staff for such excess operation at the rate approved by the Engineer-in-charge from time to time.

h) In case of breakdown, repairable at the site within a period of three days hire charges as specified in the schedule will be levied except in case of major repairs.

i) Normally the tools and plants will be supplied with operating staff.

j) The hirer shall be responsible for any claims for compensation for loss of life, injury or damage to property etc. arising due to any causes what-so-ever during the period of the machinery is in his charge.

k) All municipal or other dues and taxes payable on account of the use or operation of the tools and plants for the period of hire shall be defrayed by the hirer.

l) The hirer shall make good any loss or damages arising out of causes other than fair wear and tear to the tools and plants during the period of hire. The cost recoverable from the hirer shall be the full replacement value as determined by the Engineer-in-charge. In the event of any loss or damage not being made good by the hirer to the satisfaction of the said Engineer-in-charge the office shall be at liberty to make good himself such loss or damage and recover the cost thereof from the hirer. The hirer shall pay to the Engineer-in-charge such an amount as shall be necessary to make good the loss or damage failing which the same will be recovered from his dues as in case of hire charges.



Signature of Contractor

Superintending Engineer  
Shree Jagannath Temple

OSD (Development)  
Shree Jagannath Temple



m) On the breach of any terms or conditions of this agreement by the hirer the Engineer-in-charge shall be entitled to demand the return of tools and plants and the hirer shall return the tools and plants within 72 hours from the date of receipt of such order in writing. In case of failure on the part of the hirer to comply with such order he shall be liable to pay such penalty as may be imposed by the Engineer-in-charge for the period the tools and plant are detained provided that the maximum penalty shall not exceed the cost replacement of the tools and plants

n) In case of any disputes between the hirer and the Government, the decision of the Chief Engineer shall be final.

o) This agreement shall be operated by the Engineer-in-charge on behalf of the Government and the term Engineer-in-charge shall include all officers duly authorised by him to exercise powers on his behalf.

#### THE SCHEDULE

Serial No.	Description and Name of the articles	No.	Amount of hire per hour	Remarks

In witness where of the hirer and the Engineer-in-Charge has for and on behalf of the Governor of the State has set their respective hand, the day and the year here in above written.

Signed by:

1.

2.

2

Signed sealed and delivered in the presence of

112

#### ELIGIBILITY CRITERIA:

To be eligible for qualification, applicants shall furnish the followings. Non-furnishing of the following particulars shall be treated as ineligible.

a. Required E.M.D (Bid Security) as per the Clause No.20 of DTCN.

b. Cost of bid document towards Cost of tender paper as per Clause No.4 of DTCN failing which the bid shall be liable for rejection.

c. Xerox copy of valid Contractor Registration Certificate, GST Registration Certificate, GSTIN, PAN card along with the tender documents and the L-I bidder has to furnish the Original Registration certificate, GSTIN and Pan card for verification within (5) Five days of opening of Cover-II of the tender before Chief Administrator, SJTA, Puri as per Clause No-1, 5(i) and 21 of DTCN. The contractor belonging to outside state of Odisha and not started business should submit an undertaking in the form of an Affidavit indicating therein that they are not registered under Odisha GST as they have not started any business in the state and they have no liability under the Act. But before award of final contract, such bidders will have to produce the GST Registration certificate.


d. A) License criteria (i.e. M.O.U. with eligible registered Electrical Contractor having valid H.T / L.T / M.V license for execution of Electrical Installation work) as per Clause No.8 of DTCN and Schedule-J need to be furnished.

B) i) Bidders shall make MOU with a professional firm or body who has competence and experience in handling fire safety services.

ii) Firm must have his full fledged tools and plants, skilled man power at Odisha.

iii) The bidders who have not done MOU with Fire Protection firm will not be qualified technically.

e. (i) Evidence of ownerships of machineries/ equipments as per Clause No.7 of DTCN and need to be furnished by the bidder in Schedule-C. The tenderer must have to secure 80% marks in Plants & machineries required as per Schedule-C.



Signature of Contractor

Superintending Engineer  
Shree Jagannath Temple

OSD (Development)  
Shree Jagannath Temple



(ii) The contractor intending to hire/lease equipments/ machineries are required to furnish proof of ownership from the company/ person providing equipments/ machineries on hire/lease along with contracts/ agreements/lease deed and duration of such contract. The contracts/agreements/lease deed should be on long term basis for a minimum period of 12 (Twelve) months from the start date of online bidding should be furnished failing which the bid shall be liable for rejection.

**f. Joint Ventures are not accepted.**

g. The bidder should have satisfactorily executed at least one or maximum two nos of Similar Nature of Works means construction of building in composite manner i.e. Civil, P.H. & E.I. combinedly aggregating 33% of the estimated cost in any one Financial year during last Five financial years i.e. 2018-19, 2019-20, 2020-21, 2021-22 & 2022-23 in Govt., or Govt. undertaking organization duly signed by an officer not below the rank of Superintending Engineer / Executive Engineer or Equivalent of the concerned executing department as per Schedule-D as per Clause No. 72 (Similar Nature of Works means construction of buildings inclusive of Electrical installations and P.H. works). In case, if the work executed within the period more than one financial year, the year wise break up of amount of work executed in each financial year is to be furnished.

h. Information in scanned copy regarding current litigation, debarring / expelling of the applicant or abandonment of work by the applicant in schedule "E" and affidavit to that effect including authentication of tender documents in schedule "F" and No Relationship/ Relationship certificate in Schedule-A/ Schedule - I, existing commitments and on-going works in Schedule - B and Work Experience Certificate in Schedule -D as per relevant clauses of DTCN should be furnished failing which the bid shall be liable for rejection.

**i. Bid Capacity**

Applicants who meet the minimum qualification criteria will be qualified only if their available bid capacity at the expected time of bidding is more than the total estimated cost of the works. The available bid capacity will be calculated as under.

Assessed Available Bid Capacity=  $(A \times N^2 - B)$ , where

A= Maximum value of works executed in any one year during the last five years (updated to the current price level) rate of inflation may be taken as 10 per cent per year (escalation factor) which will take into account the completed as well as works in progress,

B= Value at current price level of the existing commitments and ongoing works to be completed during the next Nine months (period of completion of works for which bids are invited); and

N= Number of years prescribed for completion of the works for which the bids are invited.  
(for work completion period less than one year the value may be taken as one year)

**Note:** In case of a Joint Venture the available bid capacity will be applied for each partner to the extent of his proposed participation in the execution of the works.

The statement showing the value of existing commitments and ongoing works as well as the stipulated period of completion remaining for each of the works listed should be countersigned by the Engineer-in-Charge not below the rank of an Executive Engineer

**Escalation factor**

Following enhancement factors will be used for the costs of works executed and the financial figures to a common base value for works completed in India.

<u>Year before</u>	<u>Multiplying factor</u>
One	1.10
Two	1.21
Three	1.33
Four	1.46
Five	1.61

(Applicant should indicate actual figures of costs and amounts for the work executed by them without accounting for the above mentioned factors)

Signature of Contractor

Superintending Engineer  
Shree Jagannath Temple

OSD (Development)  
Shree Jagannath Temple



In case the financial figures and value of completed works are in foreign currency the above enhanced multiplying factors will not be applied. Instead current market exchange rate (State Bank of India B.C. selling rate as on the last date of submission of the bid) will be applied for the purpose of conversion of amount in foreign currency into Indian rupees.

The information on Bid Capacity as on the date of this bid is to be furnished as per the format in Schedule - B as per the Clause No. 72.

Total value of Civil Engineering construction work performed in the last five years should be furnished by bidder consolidating the financial year wise information in one page and that information should be certified by the Chartered Accountant.

2018-2019-----

2019-2020-----

2020-2021-----

2021-2022-----

2022-2023-----

Base year shall be taken as 2023-24.

113 Time Control :- (Vide Works Department Office Memorandum No.24716 dtd.24.12.2005 and No.8310 dtd.17.05.2006)

a) Progress of work and Re-scheduling programme.

i) The Superintending Engineer / Engineer-in-Charge shall issue the letter of acceptance to the successful contractor. The issue of the letter of acceptance shall be treated as closure of the Bid process and commencement of the contract.

ii) Within 15 days of issue of the letter of acceptance, the contractor shall submit to the Engineer-in-Charge for approval a Programme showing the general methods, arrangements, and timing for all the activities in the Works along with monthly cash flow forecast

iii) To ensure good progress during the execution of the work the contractors shall be bound in all cases in which the time allowed for any work exceeds one month to complete, 1/4th of the whole time allowed under the contract has elapsed, 1/2 of the whole of the work before 1/2 of the whole time allowed under the contract has elapsed, 3/4th of the whole of the work before 3/4th of the whole time allowed under the contract has elapsed.

iv) If at any time it should appear to the Engineer-in-Charge that the actual process of the work does not conform to the programme to which consent has been given the Contractor shall produce, at the request of the Engineer-in-Charge, a revised programme showing the modifications to such programme necessary to ensure completion of the works within the time for completion. If the contractor does not submit an updated Programme within this period, the Engineer-in-Charge may withhold the amount of 1% of the contract value from the next payment certificate and continue to withhold this amount until the next payment after the date on which the overdue Programme has been submitted.

v) An update of the Programme shall be a programme showing the actual progress achieved on each activity and the effect of the progress achieved on the timing of the remaining work including any changes to the sequence of the activities

vi) The Engineer-in-Charge's approval of the Programme shall not alter the Contractor's obligations. The Contractor may revise the Programme and submit it to the Engineer-in-Charge again at any time. A revised Programme is to show the effect of Variations and Compensation Events

b) Extension of the Completion Date.

i) The time allowed for execution of the works as specified in the Contract data shall be the essence of the Contract. The execution of the works shall commence from the 15th day or such time period as mentioned in letter of Award after the date on which the Engineer-in-Charge issues written orders to commence the work or from the date of handing over of the site whichever is later. If the Contractor commits default in commencing the execution of the work as aforesaid, Government shall without prejudice to any other right or remedy available in law, be at liberty to forfeit the earnest money & performance guarantee / Security deposit absolutely

Signature of Contractor

  
Superintending Engineer  
Shree Jagannath Temple

OSD (Development)  
Shree Jagannath Temple




ii) The Contractor shall submit the Time & Progress Chart for each milestone Quarter wise indicating each month and get it approved by the Department. The Chart shall be prepared in direct relation to the time stated in the Contract documents for completion of items of the works. It shall indicate the forecast of the dates of commencement and completion of various trades of sections of the work and may be amended as necessary by agreement between the Engineer-in- Charge and the Contractor within the limitations of time imposed in the contract documents, and further to ensure good progress during the execution of the work, the contractor shall in all cases in which the time allowed for any work, exceeds one month (save for special jobs for which a separate programme has been agreed upon) complete the work as per milestone given in contract data.

iii) In case of delay occurred due to any of the reasons mentioned below, the Contractor shall immediately give notice thereof in writing to the Engineer-in-Charge but shall nevertheless use constantly his best endeavors to prevent or make good the delay and shall do all that may be reasonably required to the satisfaction of the Engineer-in-Charge to proceed with the works.

- (1) Force majeure, or
  - (2) Abnormally bad weather, or
  - (3) Serious loss or damage by fire, or
  - (4) Civil commotion, local commotion of workmen, strike or lockout affecting any of the trades employed on the work, or.
  - (5) Delay on the part of other contractors or tradesmen engaged by Engineer-in-Charge in executing work not forming part of the Contract.
  - (6) In case a Variation is issued which makes it impossible for Completion to be achieved by the Intended Completion Date without the Contractor taking steps to accelerate the remaining work and which would cause the Contractor to incur additional cost, or
  - (7) Any other cause, which, in the absolute discretion of the authority mentioned, in Contract data is beyond the Contractors control.
- iv) Request for reschedule and extension of time, to be eligible for consideration, shall be made by the Contractor in writing within fourteen (14) days of the happening of the event causing delay. The Contractor may also, if practicable, indicate in such a request the period for which extension is desired.
- v) In any such case a fair and reasonable extension of time for completion of work may be given. Such extension shall be communicated to the Contractor by the Engineer-in-Charge in writing, within 3 months of the date of receipt of such request. Non-application by the contractor for extension of time shall not be a bar for giving a fair and reasonable extension by the Engineer-in-Charge and this shall be binding on the contractor.
- c) Compensation for Delay.

Signature of Contractor

  
Superintending Engineer  
Shree Jagannath Temple

OSD (Development)  
Shree Jagannath Temple



If the contractor fails to maintain the required progress in terms of clause-2 of P-1 Contract or to complete the work and clear the site on or before the contract or extended date of completion, he shall, without prejudice to any other right or remedy available under the law to the Government on account of such breach, pay as agreed compensation the amount calculated at the rates stipulated below as the **Chief Administrator, Shree Jagannatha Temple Administration, Puri** (whose decision in writing shall be final and binding) may decide on the amount of tendered value of the work for every completed day / month (as applicable) that the progress remains below that specified in Clause-2 of P-1 Contract or that the work remains incomplete. This will also apply to items or group of items for which a separate period of completion has been specified. Compensation @ 1.5% per month of for delay of work, delay to be completed on per Day basis. Provided always that the total amount of compensation for delay to be paid under this condition shall not exceed 10% of the Tendered Value of work or to the Tendered Value of the item or group of items of work for which a separate period of completion is originally given. The amount of compensation may be adjusted or set-off against any sum payable to the Contractor under this or any other contract with the Government. In case, the contractor does not achieve a particular milestone mentioned in contract data, or the rescheduled milestone(s) in terms of Clause-2.5, the amount shown against that milestone shall be withheld, to be adjusted against the compensation levied at the final grant of extension of time. Withholding of this amount on failure to achieve a milestone shall be automatic without any notice to the contractor. However, if the contractor catches up with the progress of work on the subsequent milestone(s), the withheld amount shall be released. In case the contractor fails to make up for the delay in subsequent milestone(s), amount mentioned against each milestone missed subsequently also shall be withheld. However no interest whatsoever shall be payable on such withheld amount.

**d) Bonus for early completion**

For availing incentive clause in any project which is completed before the stipulated date of completion, subject to other stipulations it is mandatory on the part of the concerned Superintending Engineer to report the actual date of completion of the project as soon as possible through fax or e-mail so that the report is received within 7 days of such completion by the concerned Chief Construction Engineer, Chief Engineer & the Administrative Department. The incentive for timely, completion should be on a graduated scale of one percent to 05 percent of the contract value. Assessment of incentives may be worked out for earlier completion of work in all respect in the following scale

Before 30 % of contract period = 5 % of Contract Value

Before 20 to 30 % of contract period = 4 % of Contract Value

Before 10 to 20 % of contract period = 3 % of Contract Value

Before 5 to 10 % of contract period = 2 % of Contract Value

Before 5% of contract period = 1 % of Contract Value

(Amendment to Para-3.5.5 (V) of Note-III of OPWD Code Vol.-I by inclusion vide O.M. No.5288 dt.04.05.2016)

**e) Management Meetings**

i) Either the Engineer or the Contractor may require the other to attend a management meeting. The business of management meetings shall be to review the plans for remaining work and to deal with matters raised in accordance with the early warning procedure.

ii) The Engineer shall record the business of management meetings and is to provide copies of his record to those attending the meeting and to the Employer. The responsibility of the parties for actions to be taken to be decided by the Engineer either at the management meeting or after the management meeting and stated in writing to all who attended the meeting

**Rescission of Contract (Amendment as per letter No.10639 dt.27.05.2005 of Works Department, Odisha):-** To rescind the contract (of which rescission notice in writing to the contractor under the hand of the Superintending Engineer shall be conclusive evidence), 20% of the value of left over work will be realized from the contractor as penalty.



Superintending Engineer  
Shree Jagannath Temple

Signature of Contractor

OSD (Development)  
Shree Jagannath Temple



- 114 Building and other Construction Workers Welfare Cess @ 1% of the estimated cost as per tender notification read with latest corrigendum if any will be proportionately deducted from the contractor's bill at the time of making payment of each bill.
- 115 The tenderers are required to go through each clause of P.W.D. Form P-1 carefully in addition to the clauses mentioned here in before tendering.
- 116 A Contractor may be black listed as per amendment made to Appendix XXXIV to OPWD Code Vol.-II on rules for black listing of Contractors vide letter no.3365 dt.01.03.2007 of Works Department, Odisha.  
As per said amendment a Contractor may be blacklisted
- a) Misbehavior/threatening of Departmental & supervisory officers during execution of work/tendering process.
  - b) Involvement in any sort of tender fixing.
  - c) Constant non-achievement of milestones on insufficient and imaginary grounds and nonadherence to quality specifications despite being pointed out.
  - d) Persistent and intentional violation of important conditions of contract.
  - e) Security consideration of the State i.e. any action that jeopardizes the security of the State.
  - f) Submission of false/ fabricated / forged documents for consideration of a tender.
- 117 The safety certificate of the E.I. work will be furnished by the agencies after getting necessary verification from the electrical inspector / equally competent authority responsible for the work prior to Energisation of the building.
- 118 Percentage rate contract (vide Works Department letter no.8310 dt.17.05.2006) In case of percentage rate tender:-
- i) The Contractor has to mention percentage excess or less over the estimated cost (In figures as well as words) in the prescribed format appended to the tender document.
  - ii) Contractors participated in the tender for more than one work may offer conditional rebate. Rebate offer submitted in separate sealed envelope shall be opened, declared and recorded first. The rebate so offered shall be considered after opening of all packages called in the same Tender Notice. The Contractors who wish to tender for two or more works shall submit separate tender for each. Each tender shall have the Bid Identification No., Name & Sl. No. of the work (as per IFB) to which they refer, written on the envelope
  - iii) Only percentage quoted shall be considered. Percentage quoted by the Contractor should be accurately filled-in figures and words, so that there is no discrepancy.
    - 1) If any discrepancy is found in the percentage quoted in words and figures, then the percentage quoted by the Contractor in words shall be taken as correct
    - (2) If any discrepancy is found in the percentage quoted in percentage excess/ less and the total amount quoted by the Contractor, then percentage will be taken as correct
    - (3) The percentage quoted in the tender without mentioning excess or less and not supported with the corresponding amount will be treated as excess.
    - (4) The percentage quoted in the tender without mentioning excess / less supported with corresponding amount does not tally with either to percentage excess or less then it will be treated as percentage excess.
    - (5) The percentage quoted in the tender without mentioning excess / less supported with corresponding amount if tallied with the percentage then it will be treated as to which side the amount tallies.
    - (6) The Contractor will write percentage excess/ less up to two decimal point only.
    - (7) The tender shall be written legibly and free from erasures, over writings or corrections of figures. Corrections, over writings & interpolations where unavoidable should be made by making out, initialing, dating and rewriting.
  - iv) In the contract P1 time is the essence. The contractor is required to maintain a certain rate of progress specify in the contract
  - v) The quantity mentioned can be increased or reduced to the extent of 10% for individual items subject to a maximum of 5% over the estimated cost. If it exceeds the limit stated above prior approval of competent authority is mandatory before making any payment.

Signature of Contractor

Superintending Engineer  
Shree Jagannath Temple

OSD (Development)  
Shree Jagannath Temple



- vi) The period of completion is fixed and cannot be altered except in case of exceptional circumstances with due approval of next higher authority.
- vii) Bills for percentage rate tenders shall be prepared at the estimated rates for individual items only and the percentage excess or less shall be added or subtracted from the gross amount of the bill.
- viii) The Contractor will quote percentage excess/less up to two decimal point only. If he writes the percentage excess/less up to three or more decimal points, the second decimal point shall only be considered without rounding off (vide Works Department O.M No- 7885 dtd. 23.07.2013.).

119 As and when need arises, the contractor is bound to produce the bills and vouchers in support of procurement of materials utilized in execution of works contract before the Engineer-in-Charge of the works.

(Total 119 Clauses) only

#### TECHNICAL SPECIFICATION OF CIVIL PORTION OF WORK

Materials of following specification are to be used in work. The Tenderers are expected to possess and be well conversant with the following IS standard and code of practice.

1.	Cement	Will be as per I.S. 269/255 (However the grade of cement to be selected by the Engineer-in-Charge of work and compressive cube test before commencement of work in each batch).
2.	Steel	I.S. 432 (Plain) and 1786 (Tor)
3.	Vibrator	I.S. 7246
4.	Aggregate	I.S. 383, I.S. 515
5.	Water for mixing and curing	Shall be clean, free from injurious amount of oil, salt, acid, vegetable materials and other substances and harmful to concrete in conformity to I.S. 456 and I.S. 2025.
6.	Sand/ Fine Aggregate	I.S. 2116, 383
7.	Binding wire	I.S. 280 (galvanized minimum 1 mm)
8.	Rain water pipe	I.S. 2527
9.	Construction joints	I.S. 3414
10.	Steel Window Frame	I.S. 1038/83
11.	Steel Door Frame	I.S. 4351/75
12.	Fitting & Fixtures for joinery works	Conforming to I.S. 7452/82 strictly conform to I.S. specification and as per direction of Engineer-in-Charge.

Note : For road work (Approach Road) specification as per road and bridges (latest edition) published by I.R.C & M.O.R.T.&H. shall be followed. In case of any doubt and absence of provision, regarding specification I.S. shall be referred (Indian standard).

#### ITEM OF WORK

- Concrete shall be with conformity to I.S.456.
- Foundation shall be with conformity to I.S.1080.
- Stone masonry (R.R.) shall be with conformity to I.S.1597 (Part-I)
- C.R. Masonry shall be with conformity to I.S.1597.
- Brick masonry shall be with conformity to I.S.2212.
- Cement plastering shall be with conformity to I.S.9103 & 6925.
- Mortar shall be with conformity to I.S.2250
- White and colour washing shall be with conformity to I.S.6278.
- CC in foundation shall be with conformity to I.S.2571.
- Anti-Termite Treatment shall be with conformity to I.S.6813. (Part - I & Part - II)
- Painting to all surfaces shall be with conformity to I.S.2395 (Part - I & Part - II)
- DPC shall be with conformity to I.S.3067
- Tarfelt treatment shall be with conformity to I.S.1346
- Mosaic flooring with conformity to I.S.2114
- Steel painting shall be with conformity to I.S.1477 (Part - I & Part - II) I.S.1661



Signature of Contractor

Superintending Engineer  
Shree Jagannath Temple

OSD (Development)  
Shree Jagannath Temple



# **TECHNICAL SPECIFICATIONS OF P.H. PORTION OF WORK**

## **A) WATER SUPPLY & SANITARY INSTALLATIONS:**

Materials of following standard manufacturers are to be used in the work. The contractor shall indicate, in the offer, the brand or make of the materials, for which the rates are quoted.

**(a) Sanitary fixtures:**

To be of best quality vitreous ware of porcelain.

**(i) Indian water closet**

**(ii) Foot Rests**

**(iii) Wash Hand Basin**

**(iv) Kitchen Sink - Hindware/Parry Ware / Neycer/ ISI marked**

**(v) Urinals**

**(vi) Drain Board**

**(vii) Odisha Closet**

**(viii) European Water Closet & Low Level Flushing Cistern.**

**(b) C.I. High Level Flushing Cisterns :**

Sushila Industries Prabhat Iron Foundry/  
East India Steel / I.S.I. marked. "

**(c) H.C.I. Soil Waste Pipes:**

Confirming to I.S.I. 1729-1954, having  
I.S.I.Mark.

**(d) C.P. Bath Room Fittings:**

Plaza/ Jaquar I.S.I. marked &  
confirming to-latest ISS

**(e) Brass Fittings :**

Shakti/Anupama /Luster/1.S.I.Marked.

**(f) Gunmetal Valves :**

Anupama / Leader / B.S.I.S.I. marked.

**(g) G.I. Pipes (Medium Class):**

Manufactured by TATA / JINDAL / B.ST.  
having I.S.I. Mark.

**(h) Galvanised Iron fittings :**

I.S.I. marked C/R brand.

**(i) Paints:**

Asian / Berger / Jonson/Confirming to I.S.S

**(j) Cast Iron Manhole cover frame:**

Sushila Industries / Prabhat Iron Foundry /  
East India Steel make confirming to ISS 7.26

**(k) Stone Ware Pipes & Fittings :**

Manufactured by Odisha Ceramic Industries  
/ Odisha Industries / Keshab Ceramic  
confirming to I.S.S. Specification No.651 /  
1980 (Grade A)

**(l) P.V.C. (S.W.R.) & P.V.C (Rigid.)  
Pipe/Fittings:**

Manufactured by the Supreme Industries  
Ltd., Bombay / Oriplast, Balasore Duroplast  
confirming to I.S. Specification No. 4985/81  
(Class IV)

## **(B) BUILDING MATERIALS:**

**(a) Bricks:**

Bricks shall be of locally available best quality kiln burnt. Bricks shall be well burnt, uniform deep red, cherry or copper colored, free from cracks and flaws, well shaped, uniform in size, homogeneous in textures and shall omit a clear metallic sound when struck, bricks shall have a minimum crushing strength 75 Kg/Cm<sup>2</sup> and shall not absorb water more than 20% by weight.

**(b) Cement Mortar:**

Mortar shall be well mixed to a uniform colour and consisting in the proportion as specified in the items of work. Sand shall be measured on the basis of its dry volume and the quantity shall be adjusted for bulking of damp sand. Cement shall be mixed, taking 50 kg. or 0.035 Cum. in volume only required quantity that can be consumed within 30 minutes of adding water shall be mixed at one time.

**(c) Cement:**

Cement should confirm to IS-269/IS-455.



Signature of Contractor

Superintending Engineer  
Shree Jagannath Temple

OSD (Development)  
Shree Jagannath Temple



**(d) Sand:**

Locally available best river sand medium size.

**(e) Coarse Aggregates:**

The coarse aggregate shall be of hard granite stone and shall generally conform to I.S. 389. Porous Course aggregate shall not be used. The aggregate shall be free from clay films and other adherent coatings. Aggregate containing clay films over the stone materials shall be thoroughly washed. The aggregate shall be from approved quarry and crusher broken. Course aggregates shall be composed of particles ranging between the sizes 2.36 to the maximum size as may be specified in the relevant item of work, within the range, the aggregates shall be well graded so as to produce a dense concrete.

**(f) Reinforcements:**

Mild steel Round Bars, coiled twisted and deformed bars of steel of medium tensile strength will be used as reinforcement as per drawing and design and directions. Mild steel bars shall conform to I.S.:226/1962 standard quality or IS:432/1966 - Grade-I. Black annealed wire (Not thinner than 24 gauge for tying the reinforcements shall be used).

**TECHNICAL SPECIFICATION FOR SANITARY & PLUMBING WORKS****(A) Sanitary ware & allied fittings :****1. General:**

All Sanitary fixtures and their allied fittings, should be of first quality, manufactured by Hindustan Sanitary Ware / Parryware / Nycer, These should be approved by the Engineer-in-charge of the G.P.H. Wing before use.

**2. Squatting Pattern W.C. (pan) (Odisha Pattern Closets):**

The water closet shall be of vitreous China of specified size and pattern, with an integral flushing rim. It shall have the flushing inlet at the back. The Odisha closet should be of approved quality confirming to I.S.S.-2656 (Part-III).

The squatting type Indian Water Closet (Odisha Closet) shall be sunk in floor sloped towards the pan in a workmanship like manner. The closet shall be fixed on a proper cement concrete base of 1.3.6 proportion, taking care that the cushion is uniform and even, without closet, to receive the specified thickness of the floor finishing. The joint between the Closet and the P.V.C. (S.W.R) trap shall be made with W.C. ring and rubber lubricant and shall be leak proof.

**3. Flushing Cistern :**

The flushing of the Indian water closet (Odisha Closet) shall be done by C.I. or Polyatrine High Level low-level porcelain valve-less syphonic flushing cistern of approved brand and quality I.S.I. Marked and capacity as specified. The connection between the cistern and water closet shall be made by 32 dia O.I. flush pipe, made from G.I. Pipe (Light Quality) or 32 dia P.V.C. Pipe as specified in the tender schedule. The flush pipe with an offset should be fixed to wall by using C.I. Holder Bat Clamps. The capacity of the cistern should be 10 Ltrs. as per I.S.S. 15 Ltrs. In case of low-level cisterns. The Cistern shall be fixed on cast Iron or Rolled Steel Cantilever Brackets (Bulltin type), which shall be firmly embedded in the wall, with C.C. 1.2.4. The Cistern shall be provided with 20mm dia P.V.C. Overflow Pipe with fittings, which shall terminate into mosquito proof coupling secured in a manner that will permit it to be readily cleaned or renewed.

The 32mm dia Flush Pipe shall be connected to the Water Closet by means of approved type joint. The Flush Pipe shall be fixed to wall by using C.I. Holder Bat Clamps. The bend and the Offset as required in the Flush pipe shall be made cold. The inside of the Cistern shall be painted with two coats of approved black bitumen paint. The Outer face of the Cistern, Brackets Overflow pipe and Flush Pipe etc., shall be painted with two coats of any synthetic enamel paint of approved shade and make, over a coat of priming. The cost of the rate quoted for the flushing cistern. The inlet connection to the Cistern shall be made with 450 mm 1 cmg 15 mm dia P.V.C. Heavy type connection Pipe.

**4. Wash Hand Basin:**


Signature of Contractor

Superintending Engineer  
Shree Jagannath Temple

OSD (Development)  
Shree Jagannath Temple



The Wash Hand Basin shall be of the White Vitreous China of approved quality, make and brand I.S.I, marked. It shall be one-piece construction with an integral combined overflow. The size of the basin shall be as specified. Each basin shall be provided with one 15 mm dia C.R Brass Pillar Tap, 32mm dia C.R Waste, C.R. Chain and Rubber Plug, Unions, Joints, C.P Bottletrap cast complete in all respects of approved quality.

The Basin shall be supported on a pair of R.S. or C.I. Cantilever brackets (built in type) embedded and fixed in wall with cement concrete, 1:2:4. These brackets shall be painted to the required shade with two coats of approved synthetic enamel paint over a coat of priming.

The waste of the Basin shall discharge into a floor trap or Channel through bottle traps as specified. One 32mm dia C.P. Bottle Trap is to be fixed to the Waste of the Basin & the outlet of the bottle trap is to be connected to the waste pipe to discharge the waste to the Pipe, to discharge the waste to the aforesaid floor trap. The inlet connection to the Basin shall be made with 450mm Long 15mm dia Heavy type P.V.C. connection pipe.

#### 5. Kitchen Sink:

Unless otherwise mentioned the Kitchen Sink and drain board (if used) shall be of white Vitreous China or fire clay as specified and approved quality, make a brand, confirming to T.S.S, It shall be of one piece construction with integral combined overflow. The size of the sink and Drain Board shall be as specified.

Each Sink shall be provided with one 15mm dia C.P. brass, Bib Cock, long body, 40mm C.P. Waste with overflow C.P. Chain & Rubber Plug, unions etc., complete in all respects as specified and of approved quality.

The sink shall be supported on a pair of M.S. or C.I. Cantilever Brackets (Built in type) embedded or fixed in position in the wall by Cement Concrete 1:2:4. The brackets shall be painted to required shade with two coats of approved synthetic enamel paint over a coat of priming. The waste should discharge into a floor Trap or Channel. The waste pipe should be 40mm dia P.V.C. Pipe jointed to the waste of the Sink with a Brass union nut.

#### 6. Standing Urinals :


The Urinals shall be flat pattern lipped front basin of required dimension of White Vitreous China and one piece construction with internal flushing box rim of an approved make and brand as specified. It shall be fixed in the position by\*using wooden plug embedded in the wall with screws of proper size. Each Urinal shall be connected to a 40mm dia RV.C. Waste Pipe, which shall discharge into a channel of floor trap. The lip of Urinals shall be kept at 525mm from floor level, while fixing the Urinal on wall.

Where no. of Urinals are fixed in a line, the distance between the centres to centre of each Urinal shall be kept 750mm. and each Urinal should be separated from one to other by a partition plate. The centre to centre of partition plates shall be kept 750mm apart. The partition plate shall be of one-piece 25mm thick marble plates, cut to size and front corners rounded. The partition plates shall be embedded in wall with cement concrete and finished smooth. The bottom of the partition plate should be kept 350mm above floor level and top should be kept at 1250mm above floor level. The plates should project 600mm from wall surface. The width of the plates to be embedded inside the wall should not be less than 100mm. The thickness of the plates shall be minimum 25mm.

For flushing the Urinals each Urinals shall be connected with one 20mm dia G.I. Pipe (Medium Class), One of this pipe shall be inserted into the inlet of the Urinal and jointed with Jute and putty where as the other end is connected either with a Tee or Bend with the 25mm dia size Water Pipe Line fixed on the wall horizontal above the Urinals. In each 20mm dia flush pipe one 20mm dia cum-metal Gate value, the water will flow to thermal of Urinal through the inlet pipe and flush the Urinal. After flush, the valve can be closed to avoid wastage of water. One 40mm dia P.V.C. Waste Pipe shall be connected to the waste of each Urinal, to discharge the Waste into the Channel of Trap. One end of this Waste pipe shall be made a cup size to fit into the projected waste and tightened with screws.

#### 7. Squatting Urinal Plates:

Signature of Contractor

  
Superintending Engineer  
Shree Jagannath Temple

OSD (Development)  
Shree Jagannath Temple



The Urinal Plates shall be of White Glazed Vitreous China with integral flushing rim of size 450 X 350mm of approved make and brand as specified. There shall be white vitreous channel with stop and outlet pieces in front. These plates shall be fixed on C.C. at 75mm to 100mm above floor level.

For flushing arrangement, one 25mm dia G.I. Common Water Pipeline (minimum size) shall be fixed on the wall parallel to floor. For each urinal one 20mm dia G.I. Branch Pipe shall be taken down up to 1200mm from floor level just at the centre of each plate, in which one 20mm dia Gate Valves is fixed at 350mm above floor level. At 1200mm height, the 20mm dia flush pipe shall be divided into two branches shall be taken downward and connected to the inlets of the urinals plate at floor level. By operating the valve as above, the water will rush into the rims of the urinal plate and flush it.

Where there are number of urinals fixed in a line, each urinal should be separated by a partition plate fixed in the centre of two urinal plates. The centre-to-centre distance of the partition plates shall be kept 750mm. The partition plates shall be of one-piece marble plate, 25mm thick, cut to sizes and front corners rounded. The plates are to be embedded in wall with cement concrete and finished smooth. The bottom of the partition plates shall be kept flushed to urinal top level and the top level of partition plate shall be kept at 1200mm from the urinal plate top and the projection from the wall shall be 600mm. The width of the plate to be embedded inside the wall should not be less than 100mm.

#### (B) Soil and waste pipes and fittings

##### 1. H.C.I. Pipe Fittings

The Cast iron Soil, Waste and design pipes (spigot & socket joints) shall be of make and brand as specified (under specification of materials), confirming to I.S.S. 3989-1970 and ISI marked with approved clamps are to be used. The pipes and fittings shall be free from cracks, laps, pinholes, and other imperfection and carefully cited. The access door fittings shall be designed and made so as to avoid dead space in which filth may accumulate and door shall be provided with 3mm thick rubber insertion packing when closed and bolted.

##### WEIGHT OF HCI PIPES

2. Dia of Pipe in mm	Thickness in mm	Length of pipe & width piece	
		1.8mtr. D/s	1.8mtr.
50 mm	5mm	16.00kg.	15.00 kg.
75 mm	5mm.	13.83kg.	16.52kg.
100 mm	8mm	24.00kg.	22.00kg.
150mm	8mm	26.70 kg.	31.82kg.
Tolerance 10%			

3. The jointing should be done with pig lead confirming to I.S. 782-1966 - grade 99.94. The spigot and of

Pipes and Fittings should enter into the socket end. The annular space shall be packed with spun yarn

gasket, compacted so as to leave a depth for receiving required quantity of lead in a continuous pouring from

ladder. After pouring lead in the joints in full, caulking is to be done three times round with the caulking

chisels, so that the joints may be sealed with lead. The depth of lead in a point should be 35mm and the rest

depth of the joint should be packed with spun yarn Gasket.

##### 4. Requirement of lead and Gasket cement for jointing H.C.I. Pipes (Each Joint)

Dia of pipe in mm.	Lead in kg.	Gasket in kg.	Cement kg.
(same for lead & cement joint)			
100	1.2kg.	0.13kg.	0.12kg.
50	0.36 kg	0.06 kg.	0.06 kg.

Signature of Contractor

Superintending Engineer  
Shree Jagannath Temple

OSD (Development)  
Shree Jagannath Temple



5. The inside of the pipes and fittings shall be well coated with special tar or bitumen solution of approved quality. Where the pipe and fittings are laid below the ground, the outer surface of the pipes and fittings shall also be painted with two coats of black anticorrosive paint of approved quality. On completion of the work, the exposed pipes and fittings are to be painted with two coats of synthetic enamel paint of approved colour & quality over a coat of red oxide primer. The cost of paint should include in the rates.

6. Soil pipes for ventilation is to be connected to the sewer at its floor and without a trap and be carried to such a height, at least above roof level, to prevent damage to health by commission of foul air. The pipe shall terminate as open and protected by a cowl.

7. The waste water pipe shall be connected with the nearest yard gully or a surface drain.

8. The traps should be of hard cast iron and should have a water seal at least 50mm deep

9. All the soil and waste pipes and fittings, after laid and fixed shall be smoke tested, to the entire satisfaction of the Engineer-in-charge. The Cost of testing is to be included in the offer. For smoke-test the materials usually burnt greases cotton waste, which gives out a clear pungent smoke, which is easily detected by sight and smell. Smoke shall be pumped to the drains from the lower end from a smoke machine, which consists of lower, and burner.

**a) P.V.C (S.W.R.) & P.V.C. (Rigid) Pipes & Fittings**

9.01. The P.V.C. (S.W.R.) and P.V.C. (Rigid), soil Waste & Vent Pipes (Spigot & Socket, & couples joints), shall be of make & brand as specified (Under Specification of materials) confirming to I.S.S., B.S.S. & DIN are tube used.

The main specification of P.V.C. Soil & Waste pipes and fitting are as below.

a) Materials - Un-plasticized Poly Vinyl-Chloride (UPVC).

b) Color - Grey

c) Dimensions -

(i) Diameter - Fittings - 75mm/110mm/63mm & 63mm.

Pipes - 75mm, 110mm, on lengths of 3 or 6 mtr.

d) Wall thickness - Fittings - Minimum 3.2mm at any port.

Pipes - As per application

For Rainwater - 75mm - 1.8 to 2.2mm, 110mm - 2.5 to 3mm

Waste & Soil - 75mm - 1.8 to 2.2mm, 110mm - 2.5 to 3 mm, 63mm -

Underground drainage with

light/NIL Traffic - 110mm - 2.5 to 3mm

Light/Nil in Heavy traffic - 110mm 3.7 to 4.3mm

e) Standard Confirming to Attributes Confirms to Standard No.

i) Fittings & Wall B.S.4514, DIN 10531

Thickness - DIN 19534 I.S.7834 - PVC (Rigid)

ii) Pipe Wall thickness - IS 4905

iii) Rubber ring - IS 5382

iv) Fitting dimensions - DIN 19531 - P.V.C.,

DIN 19534-S.W.R.

IS - 7834 V.C. (Rigid)


v) Pipe Dimensions - IS 4985

b) Laying instructions & Jointing Procedure

**1 Jointing of P.V.C. (S.W.R.) Pipes & Fittings**

Clean the outside of the pipes spigot and the inside of the sealing groove of the fitting. Apply the rubber lubricant, to the spigot end, sealing ring and pass the spigot end into the socket, containing sealing ring, until fully homed. Mark and position of the Socket edge with pencil on the pipe, then withdraw the pipe from the socket by approx. 10mm towards thermal expansion gap.

Signature of Contractor

  
Superintending Engineer  
Shree Jagannath Temple

OSD (Development)  
Shree Jagannath Temple



**2 Fixing of the Pipes and fittings on wall surface.**

P.V.C. pipes both (S.W.R.) & (Rigid), fixed on wall surface, are to be supported by P.V.C. pipe clips, specially made for these pipes, with horizontal runs, the pipe clips should be spaced at intervals of more than 10 times the outside diameter of the pipes. In vertical lines the clips are to be spaced at intervals of one meter to a maximum of two meters according to pipe diameter. •

**3 Jointing of P.V.C. (Right) Pipe Fittings**

Clean the Outside of the pipes and inside of the socket of a fitting of the inside of the couplers (where 2 plain ended pipes are jointed) of. Apply solvent cement solution, evenly and smoothly on the outer surface of the pipe end and inside surface of either the coupler or the socket and pass the pipe end into the socket of the fittings. Up to full depth of socket. In case of jointing 2 plain-ended pipes 1st. push the coupler up to half depth on the end of one pipe and the outer half of the coupler should be pushed to the end of other pipe and thus, both pipes are jointed.

**4 Fixing of P.V.C. pipes and Fittings through holes of Walls or Chajja of roofs etc.**

The Wall/concrete slots should allow for a stress free installation, Pipes and fittings to be inserted into the slots, without a cement base, have to be applied first with a thin coat of P.V.C. Solvent cement, followed by sprinkling of dry sand (medium size). Allow it to dry. This process gives a sound base for cement concrete fixation, around the pipes/fittings while mending the damages

**5 Anti-syphonage Pipes**

All the antisiphonage pipes and fittings to be used are of 63mm. If these are not available under the items of P.V.C. (S.W.R.) materials, 63mm pipes and fittings, manufactured under P.V.C.(right) materials can be used, since the raw materials for both is same.

6 All traps should have a minimum water seal of 50mm as per I.S. 5329 and IS 2556 (Part XIII). Where antisiphonage connection is required, the traps to be supplied and used should have a 50mm antisiphonage vent horn on the outlet side. All the Traps used with the closets, should be of the size 125mm X 110mm i.e. Inlet (Socket end) of 125mm & outlet (spirit end) of 110mm only.

**7 Installation of Water Closet**

Determine the correct Location of the P/S Trap & set on a firm base, relative to the floor finish by pouring concrete on a slab. Bedding can be carried out by pouring concrete around the trap, ensuring that the traps outlet is left clear of concrete. Place the W.C. Connector ring to the socketed end of 125/110mm R/S trap. Apply rubber lubricant on W.C. Connector ring as well as outer side of water closet (connection point) and now complete the joint by pushing the W.C. to home of 125mm socket of the trap.

**8 P.V.C. (Rigid) Pipes and Fittings**

63mm (O.D.) P.V.C. Pipes to be used for these work either in antisiphonage system or elsewhere, should be of "Quick Fit" Pipes Class 2 (4kg. F/Cm<sup>2</sup>), Quick Fit, Pipes have one end socketed. The P.V.C. (Rigid) fittings, such as 63mm elbow, 63mm equal Tees 110mm x 63mm reducer etc. used in the work, should be of injection-molded fittings.

9 One 'jointing rubber ring will be available, with each P.V.C. (S.W.R.) pipe and fitting and hence, the cost of therein will not be added in the joint.

**10. Measurement**

All pipes shall be measured not/length as laid or fixed and shall be measured over all fittings such as bends, junctions, traps etc. The length shall be taken along the center line of the pipes and fittings. Fittings will be counted extra over.

31. Before fixing and painting, the pipe shall be tested hydraulically to pressure 0.4Kg/Cm<sup>2</sup> for pipes under I.S.-1729/1964 and at a pressure 0.7 Kg/Cm<sup>2</sup> for pipes under I.S. 3989-1970 without showing any sign of leakage, sweating or other defect of any kind. The pressure should be applied internally and shall be maintained for not less than 15 seconds.

**c) Water Supply Pipes and Fittings:****1. Materials.**

Signature of Contractor

  
 Superintending Engineer  
 Shree Jagannath Temple

 OSD (Development)  
 Shree Jagannath Temple



All galvanized Iron Pipes are to be of mild steel continuous welded, screwed tubes, medium quality conforming to I.S.S. and bearing ISI Marks manufactured by reputed Firms and approved brands as specified. The pipes shall conform to LS.1239 (Part-I) -1975. All G.I. Fittings shall be of 'R' Brand manufactured by M/s. R.M. Engineering Ltd., Ahmedabad and 'C' brand manufactured by Present Engineering works or equivalent best quality.

## 2. Laying of Pipes

The layout of the mains and service pipe set etc., will be done in accordance with the drawings. The contractor is to mark out the exact position of the pipes and fittings at site and take approval of the Engineer In-charge, before taking up the work.

3. Where the Pipes are laid, underground these must not be laid less than 450mm below ground level and coated with one coat of approved black bituminous paint. For laying the G.I. pipes and fittings 68 below ground level, the width and the depth of the trenches for different dimensions for the pipes shall be given as below :

Dia of Pipe	Width of Trench	Depth of Trench
15mm to 50 mm	300 mm	600 mm
65mm to 100mm	450 mm	750 mm

The pipes shall be laid on a layer of 75mm thick sand and filled up with sand up to 75mm above pipes and the remaining portion of the trench shall then be filled up with proper ramming as described in "Excavation and refilling". The surplus earth shall be disposed of as directed.

Thrust or anchor blocks of cement concrete 1.2.4 in hard granite chips shall be constructed on all bends or branches to transmit the hydraulic pressure without impairing the ground and spreading it over a sufficient area. Pipes shall not be laid to pass through manholes, catch pit, drain, where, it is unavoidable the pipes shall be carried in sleeve pipe of M.S./G.I., as approved by the Engineer-in-charge. The rate should include such a situation.

4. Where Pipes run along walls, the same are to be fixed to the wall with holder bat clamps / M.S. Hooks as below:

Dia of pipe in mm	15	20	25	32	40	50
Horizontal line	2m	2.50m	2.50m	2.50m	3m	3m
Vertical line	2.5m	3m	3m	3m	3.5m	3.5m

Where the pipes are passing through the R.C.C. / Masonry wall / Column / beam or pillars, these must pass through the appropriate higher sizes of C.I./G.I Sleeve Pipes and are to be included in the rates. In case the pipes are embedded in walls and floors it should be painted with one coat of anticorrosive paint of approved quality. ,

All pipes should be fixed horizontal and vertical. For taking the pipes through the walls and floors & roof slabs etc. the holes shall be made by filling with chisels or jumper and not by dismantling the brickwork or concrete. After fixing, the holes shall be made good with cement concrete 1:2:4 and properly finished with C. Plaster 1.4 to match the adjacent surface. Union Nuts are to be provided in each of the vertical riser or drop on and from G.I. Tank and near the Valve and as and where necessary. The long screw fittings of 3 mtrs. for long horizontal lines and inside the lavatory / Kitchen etc.

5. After laying and jointing the pipes and fittings shall be inspected under working condition of pressure and flow. Any joint found leaking pipes should be removed and replaced without extra cost. The pipes and fittings after they are laid shall be tested to hydraulic pressure of 6 Kg/Cm<sup>2</sup>. The test pressure should maintain without loss of for at least half an hour.

## 6. Painting

On completion of the test, the exposed pipes and fittings are to be painted with two coats of synthetic enamel paint of approved color and brand over a coat of priming.

Signature of Contractor

Superintending Engineer  
Shree Jagannath Temple

OSD (Development)  
Shree Jagannath Temple



## 7. Measurement

The length shall be measured in running meter. Correct to centimeter for the finished work, which shall include the pipes and fittings such as Bends, Tees, Elbows, etc., but excludes brass or Gun-metal fixture like tap, Cooks, Valves, PVC connection pipes etc.

## 8. Ball Valve

The ball valve shall be high or low pressure class as stipulated in the Tender Schedule and shall confirm to I.S. 1703-1968, The nominal size of ball valve shall be that corresponding to the size of Pipe for which it is used. The Ball valve shall be of brass or gun-metal and the float for low pressure polyethylene and for high pressure in copper. Each and every ball valve while in closed position shall withstand and internally applied hydraulic pressure of 20 Kg/Cm<sup>2</sup> for a minimum period of two minutes without leakage or sweating.

Every high pressure ball valve when assemble in working condition, with the float immersed to not more than half its volume shall remain closed against a test' pressure of 10.5Kg/Cm<sup>2</sup> and a low pressure ball valve against a test pressure of 5.3 Kg/Cm<sup>2</sup>.

Polyethylene floats shall be watertight and non-absorbent and shall not contaminate water and with do jointing adhesive jointing parts. The minimum thickness of the copper sheet used for making copper floats 69 shall be of 0.45 mm. The thickness of materials of the float shall be uniform throughout.

## 9. Ferrule

The ferrules for connection with C.I. main shall generally confirm to I.S. 2692-1964 and shall be of nominal bore as specified. The ferrule shall be fitted with 3 screw and 1 plug or valve capable of complete cutting off the supply to the connected pipe as and when required. For fixing the ferrule, the C.I. main shall be drilled and tapped during non-supply hour at 45 to the connected Pipe as that when required. The ferrule must be so fitted, that no portion of the sunk shall be left projecting within the main on which it is fitted. After the ferrule is connected, one C.I. bell mouth cover or with bricks (as specified) shall be kept over the ferrule to cover the ferrule to protect it and the cost thereof is to be included in the item, even if there is no mention.

## 10. Non-return Valve (Check Valves)

The non-return valve shall be of Brass or Gunmetal and shall be of horizontal or vertical flow type and of the size as specified and confirm to I.S. 7810-1959 and I.S. 778-1957. The approximate weights of the valves are given below.

Dia in mm	Horizontal type (in kg)	Vertical type (in kg)
15	0.30	0.25
20	0.55	0.25
25	0.90	0.75
32	1.25	0.90
40	1.70	1.20
50	2.90	1.45
65	5.25	2.15
80	7.70	4.10
	<b>±Tolerance 5%</b>	

## 11. Foot Valve

Foot valve is generally placed at the lower end of the suction pipe of the centrifugal pump to prevent the suction pipe from emptying. On vertical non-return valve may also be fixed in place of foot-valve. The foot valve shall confirm to I.S.038-1967.

## 12. Water meters (Domestic types)



Superintending Engineer  
Shree Jagannath Temple

Signature of Contractor

OSD (Development)  
Shree Jagannath Temple



Water meter up to 50mm nominal size shall conform to I.S.-779-1968. The meter body shall be of bronze/ Gun-metal and marked to read in liters complete with registration box and lid. The water meters shall be provided with Strainers. Strainers shall be of material, which is not susceptible to electrolyte, clean and shall be fitted on the inlet side of water meter. It shall be possible to remove and clean the strainer and not permit disturbing the registration box. The offer should include the same. The water meters shall bear ISI Mark.

### 13. Bibcock & Stopcock

These shall conform to I.S.781-1967 and bear ISI Mark. The bibcock is a draw off tap with a horizontal inlet and free outlet and stopcock is a valve with a suitable means of connection for insertion in a pipeline for controlling or stopping the flow. This shall be of screw down type. The cock shall open in anti-clockwise direction. The stopcocks should be of C.P open type/concealed type/angle valves type as specified in tender schedule. Bibcock should be also C.P Brass bibcock.

### 14. Full way Valve (Brass)

Full way valve is a valve with suitable means of connection for insertion in a pipeline for controlling or stepping the flow. The valve shall be of brass fitted with a cast-iron wheel and shall be of gate valve type confirming to I.S, 780-1960, opening Full way and of the size as specified.

Dia in mm	Flanged End Valves in kg	Screwed End Valve in kg
15	1.021	0.567
20	1.503	0.680
25	2.498	1.077
32	5.232	1.559
40	6.082	2.268
50	6.691	3.232
65	10.149	6.840
80	13.281	8.845

### 15. Gun Metal Full way Valve

This shall be of the Gun-Metal fitted with wheel and shall be of Gate-Valve type opening full way. This shall conform to I.S, 778-1971. Class I. The Valves should bear ISI Mark.

#### TECHNICAL SPECIFICATION FOR STONEWARE PIPE ETC.


#### 1. Stoneware Pipes (Materials)

The S.W. pipes & fitting should be of Grade 'A' confirming to I.S 651/1965. The pipes shall be sound, free from visible defects such as fire crack or hair crack and flow or blister. The pipes shall give a sharp clear line when struck with a light hammer and should be perfectly salt glazed.

Internal dia of Pipe in m.m.	Thickness of the Barrel in m.m.	Weight of each pipe in kg.
100	12	14
150	16	23
200	17	33
230	19	44
250	20	52
300	25	79
350	30	100
400	35	125
450	38	147

The length of pipes is 600mm exclusive of the internal depth of socket.

Signature of Contractor

  
Superintending Engineer  
Shree Jagannath Temple

OSD (Development)  
Shree Jagannath Temple



## 2. Excavation of Trench for laying Sewer Pipes

The trenches for the pipes shall be excavated to the lines & level as directed. The bed of the trench shall have to be evenly dressed throughout from one change of grade to the next. The gradient is to stout by means of sight rails and boning rods and required depth be excavated at any point. The depth of the trench shall not less than one meter, measured from top of the pipe to the surface of the ground under roads and not less than 0.75m elsewhere. The width of the trench shall be the nominal diameter of the pipe plus 350mm. The bed of the trench if in soft or made up earth, shall be well watered and rammed before laying the pipes and the depressions if any shall be properly filled with sand and consolidated in 200mm layers. Depending on soil condition, piling may even be necessary if so desired by the Engineer In-charge. If rock is met with, it shall be removed 150 mm below the level of the pipe and the trench will be refilled with sand and consolidated.

The excavated materials shall not be placed within One Mtr. or half of the depth of the trench whichever is greater from the edge of the trench. The trench shall be kept free from water. Shoring and shuttering shall be provided wherever required. Excavation below water level shall be done after dewatering the trenches.

After the excavation of the trench is completed, foundation of cement concrete 1.4.8 in hard granite metal (size 40mm) shall be laid with proper level all along under the length of the pipe with launching on all around concrete as per drawing.

## 3. Laying, Jointing, haunching of the Pipes and fittings.

Drain Pipes (S.W. pipe & other pipes used for drain and Sewer) shall be laid in straight lines and to the even gradients as shown in the layout drawings. The socket and of the pipes shall face stream. Adequate care shall be exercised in setting out and determining the level of the pipes and the contractor shall provide suitable instruments, templates, sight rails, boning rods and other equipments necessary for the purpose. In the case of pipes with joints to be made with loose collars, the collars shall be slipped on before the next pipe is laid. In those joints, a tight ring of twisted tarred jute soaked in cement mortar filling to ensure proper alignment and prevent. Cement entering the pipes, Cement compound joints is to be inished with proportion 1.1 with 45 beveling. The joints are to be kept wet with wet bag until the same are properly set with. The cement mortar joints shall be cured at least for 7 (Seven) days.

In the case of S.W. Pipe joints (socket & spigot), they should be caulked first with tarred jute (Spun) of required diameter, almost quarter depth of the socket, after which cement mortar 1:1 is pushed in with wooden chisel and finishing beveled at outside at 45 degree. Instead of jute of hump rubber gasket of proper size may also be used. The whole joint must be cured for not less than three days. In case of pipes less than 250mm dia, joints should be made at ground level with three pipes at a time and for larger ones two pipes at a time and after curing they should be soiled in foundation with the help of the ropes. All pipes should be properly launched with cement concrete 1.3.6 with washed gravel where the pipes are crossing the drain or all round concrete 1.3.6 with washed gravel is to be done to 150 mm thick over the barrel of the pipe. The whole of the drain work shall be tested when laid, and at the completion of the contract, to the satisfaction of the Engineer-in-charge and shall be retested if necessary until found satisfactory. The test shall be made by means of water under pressure at the highest point of the Section under test and providing an air pipe at the lower and of the line. Maximum head of 5 (five) fact (1.5m) must be maintained.

## 4. Excavation and refilling.

Excavation for drain and pipe trenches shall be straight and to correct depth and gradient. The trench bottom shall be of required width as per specification to allow working space for pipe jointing.

Excavated materials shall be dumped away from the site as directed by Engineer-in-charge. Suitable precautions are to be taken to prevent in flow of water into the excavated area, during construction.



Superintending Engineer  
Shree Jagannath Temple

Signature of Contractor

OSD (Development)  
Shree Jagannath Temple